

7<sup>th</sup> Stand. Par. through R. G. W.

80.<sup>00</sup> Set white limestone - 14x10x5, 5' in ground.  
3 notches E & W, edges, for. cor. 33-34. Red pine 16" dia  
N. 20° W. 25 lks. Red pine 14" N 58 E 30 lks. Red P.  
6" S 10° W. 40 lks. R. P. 20" S 58 E 20 lks. Timber  
Pine, Fir & Aspen. Aug. 27-1874

Ti. along S. bed 34. Va 16° 35 E.

6.<sup>00</sup> Top. ridge. NE & S.W. 60 ft high.

23.<sup>00</sup> Divide bet. Main Can. & Prattatts Fork. N. 20° E

40.<sup>00</sup> Set. Vol. Stone 16-12-5-9" in ground. 1/4 on N. side.

Asp. 12" dia S 15 W 15 lks. Asp. 6" dia N 39 W. 30 lks.

45.<sup>50</sup> Asp. 14" dia.

70.<sup>00</sup> An opening in timber. 30. a. & meadow.

80.<sup>00</sup> Set. Vol. Stone 16x14x8-8" in ground, 4 notches W. 2 E, edges.

For. cor 34-35. Asp. 6" dia S 15 W 13 lks. Asp. 8" dia

N. 30° E 50 lks. Asp. 5" dia N 25 E 115 lks. Asp. 6" dia

N 22 1/2 E 115 lks. Land gently rolling soil 1<sup>st</sup> rate

Timber in abundance. Fine Fir, & Aspen.

Ti. on S. bed, 35. Va 16-40 E.

2.<sup>00</sup> Leave opening. Enter timber.

5.75 Porowan Cr. 10 lks. N 15° E. in Prattatts F.