

7th Stand. Par. through R. 9. W.

of Parowan Cañ. beg. to ascend hill, enter burnt
timber.

32.00 Top of ridge, E. side of Braffitts Fork. N. 10° W.
Enter high rolling table land, leave burnt
timber.

40. Set Vol. Stone 18x12x8 12" in ground, 7/16 on
N. side. Fir 15" N 40° W 15 lks. Asp 10" N 15° E 20 lks.

45.06 Leave timber, enter meadow. N + S. abt 10.0.
Pond or spring lake at N + S. End.

49.50 beg to ascend hill, enter timber.

54.00 Top of ridge. N + S. 30 ft. high.

54.56 leave timber and hill, enter meadow. bears 1/4 S

60.00 leave meadow, 20.0. line passes through Cent.
enter timber N + S.

71.25 Leave timber, enter meadow, 7/10° W. + S. 50.0.

80.00 Set Vol. Stone 18x14x10, -12" in ground 5/16 N. 41. N. E.
for. cor. 35-36. Asp. 17" N 12 1/2° E 20 lks. Asp. 4" 7/15° W
30 lks Asp. 5" S 85° E 3 lks White Pine 12" dia 5 1/2" W
30 lks, Soil 1 1/2" rate. cor. in edge of timber.
Timber. Pine + Aspen.