

6.  
7<sup>th</sup> Stand. Par. South through R. 7. W.

N. on S. side Sec. 31. Va. 16°-30' E.

10.<sup>00</sup> Enter dense undergrowth.

40.<sup>00</sup> Set Vol. st. 24, 15, 12 - 16" in gr. for stand 1/4

Sec. Cor. Mar, S. C 14 on N. Face, mid stone, along

Pine 18-20 lks. nkd 1/4 S. B.T. no other trees.

47.50 Ridge N.E.

60.10 Can. drains N.

80.<sup>00</sup> Set Vol. rock 30x16x6-20 ins in gr. for

Stand. Cor. to Tps. 35. S. Rs 7-8. W. Marked

S.C. 46 notches E. N. & W. edges. Pine 10" S 62° W

30 lks. Pine 12" N 79° W 22 lks. Pine 10" N 5° E

21 lks each marked with proper Sec. T<sub>p</sub> & R.

Mountainous, Soil 4<sup>th</sup> Timber, scant.

dense undergrowth. Sept 24-1883

This Stand runs over the Panquitch  
Lake bottom, excellent ag. land.

From the Stand, Cor. to Tps 35. S. R 7-8 W

recently set by me I run west on

S. side of Sec. 36. Va 15-30' E