

7th Stand Par. S. through R. 8. W.

- 20.⁰⁰ Leave heavy timber
- 36.⁰⁰ Ridge bears S.
- 40.⁰⁰ Set vol. stone 15x9x6-10 in ground for St. 1/4 cor. mk S.C. 1/4 on N. face. raised mid stone alongside.
- 45.⁰⁰ ascend, enter heavy timber.
- 62.⁰⁰ Top of ridge bears NE+S.W. descend.
- 80.⁰⁰ Set vol. stone 17-12-6, 12" in ground, for St. co to Sec 2 1-2-35-36. mk s.c. 1 notch E. S. W. edges. raised mid stone alongside. Asp. 8-7112°W 18 lks. - Asp. 6-N45 E. 32 lks. Asp 9-S25°E. 13 lks. each mked. to Tp. R. 4 S. Heavily timbered + mounds.
11. on S. side Sec 35. 17. 15°-30 E
- 10.⁰⁰ Ridge N+S.
- 28.⁰⁰ Ravine N.
- 40.⁰⁰ Set vol. stone 15-10-4: 10" in ground for St. 1/4 cor. S.C. 1/4 on N. mid. stone. Pine 6-7185-W. 15 lks. mk. sign on trees