

7th Stand Par. S. through R. 8. W.

E. 1 notch W. edges. Asp. 8-N-4°E, 10 lks
 Asp. 7-S20E 20 lks. Asp. 6-N60W 15 lks,
 Asp 10. S30W, 25 lks. each mkl.

Heavily timbered,

W. on S. side 31. Va. 15-30' E.

5.00 Can. drains S. E.

40.00 Set Lava Stone 15X10X9-10" in ground
 for St. 1/4 Cor, SE 1/4 on N, Asp. 6 N-8 lks
 Asp. 5 S30°E 25 lks, each mkl.

50.00 Leave green timber, enter dry timber.

78.00 Creek 7 lks W. in Canon. N.W.

91.50 Ridge N+S.

125.00 Hollow N.

129.50 Ridge N+S.

140.00 Rav. N.

161.90 On ridge N+S, intersect E bdy, Tps.
 35 S. R. 9. W. 50 chs, N. of Stand Cor
 To Tps, 35-S. R. 8-9. W. Apt of intersection
 Set Sand Stone 14X10X4-10" in ground