

N. hdy. Tp. 38-S, R. 8-W.

From the cor. to Tpc³⁷⁴, 38-S, Rs. 8-9, W.

I run N 89° 42' E, bet Sec 2 6-31, on
a true line V 15° 12' E.

- 3.50 Enter timber and ascend, course N 75°
5.00 Plateau about 20 ft above Sp. cor,
29.80 descend abruptly.
31.80 Gulch 100 ft deep, S 30° E.
32.00 a wagon road S 30° E
32.30 Ascend abruptly.
36.58 Plateau abt 100 ft high above gulch
37.45 Sect. Linn. stone 20x10x5-14. 1/4 cor,
Fir 20-S 52 E. 45 lks. - Fir 10-N 44 W. 24 lks.
77.45 Sect. Blk. basaltic rock. 20x18x14-14.
for cor. Sec 2 5-6-31-32. 1 notch N. 5 E. edge
Asp. 12-S 11 E 15 lks. - Asp. 4-N 50 W. 2 1/2 lks
Asp. 12-S 76-W 3 1/2 lks - narrow road stone
along side. June 9-1892.

N 89° 42' E bet 5-32. V 15° 1' E

7.50 descend abruptly.