

N. Bely Tps. 38-S. R. 8. W.

- 35, Leave timber, enter park N+S.
- 40.00 Set Black bas. rock. 20x10x5 - in stone
pile 1/4 musid mid stone alongside.
Pile impracticable.
- 42.00 enter lava bed. - S.W.
- 75.00 Enter scat timber N+S.
- 80.00 Set black basaltic rock, 24x10x8,
in stone pile. for cov. Sec^s 1-2-35-36
5 notches N+1 notch E. mid stone alongside
Few scatt pine, undergrowth Juniper.
-
- 789° 42' E in tree line, lat, Sec^s 1-36 -
Mar Dec. 16-42
- 5.50 Leave scat. timber, enter lava bed, S.E.
- 40.00 Set black bas. rock, 20x10x8, in stone pile
1/4 cov. paired mid st. alongside. Pile impracticable
- 54.00 Enter scat. timber S.E.W.
- 60.00 Leave scat. timber, enter lava bed, S 20° E.
- 80.00 Cov to Tps. 37-38 S. Rs. 7-8 W.
The S. line of this Tpo. has been extremely difficult