

N. Bdy Tp. 38-S-R. 8- W.

to measure, and in some places dangerous to travel over, Wm Lewman, D.S.

July 11-1892,

N. Bdy Tp. 38-S. R. 9, W.

From the cor. to Tps. 37-38-S, Rs. 9-10 W.
 Trun. N 89° 57' E. on a true line bet. Secs 6-31. Va 15° 12' E.

Through timber and dense oak brush.

- 8.92 creek 11/2 m. S.
- 10.38 Ascend abruptly 400. Ft.
- 16.80 Top of Plateau. N. 7 S.
- 31.77 Old road, S 10° E & N.
- 38.75 Set sand. S. 24 x 8 x 3-18. 1/2 cor. Pits E & W, mlst. & earth. alongside
- 44.60 descend abruptly. 80. Ft.
- 45.80 dry wash 28/2 m wide S.
- 49.90 Ascend abruptly 80 ft.
- 52.10 Top of Plateau. N 7 S.