

## F. Body, Tp. 36 S. R. 10 West

Survey Commenced May, 11-1881.

Jas. H. Martineau

From cor. to Tps. 36-37. S. Rs 9-10 W. Iron

N. bet. Secs 31, 36. Va 15245 E.

40.00 Set Sandstone 12x10x8 in mid stone 1/4 cor

74.00 Set sandstone 15x10x4 in mid stone. 1/2 notch

S. 5 notches N. + W.C. for Milrose cor. to cor. of Secs

25-36-30-31. on S. side of chasm abt 300. ft

deep. N.E + W. perpendicular sides.

set 2 flags on line to.

80.00 point for cor. is on bottom of deep chasm  
cannot be set. thick brush, no timber

Passed to N. side of chasm on line on  
edges of same. set sandstone 14x12x8  
in mid stone, marked W.C. for Milrose  
cor. to cor. of Secs 25-30-31-36. 1 notch E. 5 N.

4 from point 2.60 chs. N. of said W.C. mark  
W. 7.00 chs. for base from which point  
flag at W.C. on S. side chasm runs