

Fr. Pody Tp. 36 S-R. 10. W.

321-40E gives for dist. 17.62 making
dist bet. W. Cors. 15.02 chs, therefore the
W. C. on N. side of chasms 9.02 chs. N.
of point for cor. to Sec^s 25-30-31-36.

N. Port Sec^s 25-30 Va 15°-45' E

- 9.02 W. C. on N. side deep chasms. Ascend
40.00 Set sand stone 15x10x8 - in mid stone
for 14 cor. on Mountain slopes E.
61.00 Top of ridge, course E & W.
80.00 Set Sand st. 18x12x6 - mid st. 2 units
S-4. N. Cor. 24-25-19-30. near bottom
of Hollow. W.

N. Port. 24-19 Va. 15°-45' E.

- 40.00 Steep ascent. Set Vol. stone. 12x12x10.
with mid stone for 14. cor.
54.00 High ridge. S70° W.
80.00 Set Vol. st. 18x12x10 in mid. Stone. 3 units
N48. cor. to Sec^s 13-24-18-19