

E. Body T37-S R. 10 W.

- 40.00 Set Sand St. 16x8x8-11. 1/4 cr. Red
P. 12-785 W. 18 lks. - Red P. 6-570 W. 30 lks.
- 40.40 Branch Coal Cr. 5 lks. N.W.
- 40.90 Leary Cr. bott. and timber
- 58.00 A. Sand St. ledge 10 ft high E & W.
- 80.00 Set Sand St. 18x10x5-13. 5 notches
S. 1 notch N. for cor. Sec^s 1-12-6-7
Cedar 12-545° E. 42 lks. - Cedar 10-745° E
10 lks. -
- N. Post Sec^s 1-6. V 15-58 E
- 2.50 White Pine 8" on top of sharp ridge E & W,
sand stone formation. black surf.
- 18.75 Red Pine 14" diam
- 40.00 Set sand stone - 16x12x4.-11. 1/4.
Asp. 4-E 30 lks. - Asp. 4 W. 25 lks.
- 44.75 dry badq expts descend N.W.
- 46.00 Leary Cr. bott. and timber
- 76.00 Top of ridge SE-N.W.
- 80.00 Set Sand Stone 30x12x4 - in mound
of stone. marked 6 notches N.E. S.W. Edge.