

First Pkly, T. 41. S. R. 13. W.

From the cor. to T. 41-42 S. R. 12, 13 W.

Run N. bet. Secs 31-36. $Va 16^{\circ} E$

22.50 Rocky Wash drs N.W.

40.00 Set limestone 12x9x5-8 $\frac{1}{4}$ cor. mid. St.

50.00 Enter breaks, formed by gulches, leading Rio Virgin

80.00 Falls in breaks, not set. therefore at 50.00

set limestone 16x10x6 marked 1 notch S.E.N.

W.C. for Milwasa cor. to cor. Secs. 25-30-31-36

N. Post 25-'30 $Va. 11^{\circ} E.$

Note, as it is impossible to chain this line

Set. flag on N. breaks of Rio Virgin. and

from W.C. 30. chs S of cor. to Secs. 25-30-31-36

was. base E. 40. chs. from which point

said flag bears $N. 15^{\circ} 13' W.$ I also

was. base from same W.C. E. 80.00

from which point said flag bears

$N. 28^{\circ} 33' W.$ gives mean dist. of flag

from W.C. 147.04 chs. I was

S. 37.04 chs. to Sec. cor.

80.00 Set. trachyte. 16x10x9-10. cor to 1424