

T. Body T. 42 S. R. 13. W

- 40.00 Sand S. 22X12X2-15. md St. 1/4 cor.
- 80.00 Sand S. 26X10X2-18. notched md St,
cor. Sec 5 7-12-13-18. no timber
-
- S. Post 13-18 Va. 16° E.
- 40.00 lime. 20X14X4.15 md ^{earth 4 pits} ~~st.~~ 1/4 cor
- 59.00 road N.W.-S.E.
- 61.00 " N.E.-S.W.
- 65.00 lime kiln 75 lks W.
- 65.15 deep wash. N.W.
- 65.60 fence N.W. S.E. side field + orchard.
- 78.00 top of cellar, Workman. House 75 lks E.
another house 3.50 N.E. of Workman.
- 79.25 fence N.E. S.W., leave field + orchard
- 80.00 Sand. 30X12X12-21. md St. Cor. 13-18-19-24.
S. Post. 19-24 Va. 16° E.
- 0.70 fence N.E. S.W.
- 1.10 " N.W. S.E.
- 2.10 Sp. Pr. N.W.
- 4.00 foot Bas. bench. N.W. S.E.
- 4.25 top near Mogie Village remains