

Thursday, 5-12

Meanders of R. back. Rio Virgin, through Sec 13, I. beg. at the M.C. on far track Sec. 13-14 on N. bank of Riv and runs with meanders up St. road through Sec. 13, 12<sup>0</sup> ditch.

N 66° 45' E 3.50 chs      Lat 1.33    Dep. 3.22  
at 3.12 fence on N. side constrains 72° 20' 30" for a distance of 3.95 chs. and then bears 71° along N. side of St.

3.50  
3.12  
---  
.38

N 42° E 7.50 chs      Lat, 5.57    Dep. 5.01  
at 1.00 ch road runs S. across river to the good ford. at all times. 3.03 fence on E. side of main St. road bears 71° 15' W, 127 chs. to and then runs W. along N. side of St.

7.50  
3.03  
---  
4.47      7.50  
1.11  
---  
6.39

at 4.33 runs through grass on slope bears track 74° E 7.25 cross runs fence bears 73° 35' E. line runs along S. side of cultivated land occupied by Larson

N 15° E 3.00 chs.      Lat 2.90    Dep. 0.75  
fence runs parallel to line of 6 ft. N. line runs along S. side of cultivated land occupied by Larson through