

Thence I run with meanders
through Sec. 12,

N 20° E 6.50

lat 6.11 dep. 2.22

line runs along 50 banks E. of foot of
old banks 10 ft high, white clay
end of line 75 lks E. of Bloomington Canal
at 5 chs. have cultivated fields
from S.W. at end of line high banks
bear N 3° W. alt 20 chs. thence N.E.

N 34° E 34.00 chs

lat 28.19 19.03

over grassy bottom over brack, 2 ft
above table water, grassy land

N 28° W 6.00

lat 5.30 dep. 12.82

line runs over sandy banks 1 ft high
at end of line Bloomington Canal is 2 ch
N. on bluff

N 22° E 5. chs

lat 4.64 dep. 1.97

line passes over sandy land banks 3 ft high
at end of line Canal is 3 chs N.