

Meanders at Right Bank of Rio Virgen  
down stream through Sec 14, T. 43-S R. 16-W.  
I begin at the meander for tract Secs 13-14  
on N. bank of river, and run with meanders  
in Sec. 14.

566° 45 W. 4.50 chs. ✓ Lat. 1.73 dep. 4.14  
at 1 ch. fence to W. line runs along  
grassy banks 15 ft high.

S 83° 00' W. 11.50 chs ✓ Lat 1.40 dep. 11.42  
line runs over sandy, quartz, banks 1 ft high  
at 5.50 intersect N. line of Larrea runs  
North & E wire fence line SW. 77 E, abt. 1 ch  
N. of this line

N 70° W. 22.00 ✓ 7.52 20.67  
line runs over sandy, quartz, land  
banks 1.5 ft high, wire fence W. about 1 ch  
N. of line