

Nov. 26-1902.  
Survey for Abraham Maw  
at  
Plain City - Weber Co

in S.W. 1/4 of Sec. 23, T. 7. N. R. 2. W.

See also.  
Field Book N-10, 26-27.  
" " J. 45-46  
" " I-97-  
" " G-15  
Plat Book. page 126.

The Lat. & Dep. of the Distance  
from the S.W. cor. of the Sec. 23  
to the Cor. place 8 1/2 mi. 533.28 ft.  
the course N 88° 23' E.  
Lat 15.94 Dep 533.1 ft.

31° 49' 30"  
S.W. cor.  
Sec. 23-  
T. 7. N. R. 2. W.

Traverse Table of above survey.

course	Dist.	N	S	E	W	L	D	D.M.D.	
N 88° 23' E	791.5	223			791.7		+ 22.3	+ 790.4	
N 0° 20' E	1045.2	1045.1			6.1		+ 1044.5	+ 5.9	
N 89° 40' W	35.7		0.2			357	+ 0.2	- 35.8	
S 40° 10' W	365.0			278.8	235.4		- 279.1	- 235.8	
S 26° 30' W	434.0		388.2		194.1		- 388.5	- 194.4	
N 78° 41' W	153.1		30.0		150.1		+ 30.0	- 150.3	
S 22° 44' W	465.6		429.4		179.9		- 429.4	- 180.0	
double		single		single					
	10976	1096.9	797.3	795.2	2.1				

17675.92	859699.32
1687308.15	332147.50
311.86	
15309.00	
	77292.00
1690554.43	768158.82
768158.82	
292345.61	
560	461197.80

10.58 acres.

Correct description of the above tract to be conveyed by A. Maw to J. Thomas, as follows  
Pt. A. S.W. 1/4 of Sec. 23, T. 7. N. R. 2. W. S. L. M. -  
Prod. of point on S. line of said Sec. 533.28 feet E.  
from the S.W. cor. of said Section running thence E. along  
the Sec. line 791.52 feet, to a point 49.1 feet  
W. from the S.E. cor. of the W. 1/4 of said 1/4 Sec.  
Thence N 0° 20' E. along fence 1045.2 feet - thence  
N 89° 40' W. 35.7 ft. thence S 40° 10' W. 365.0 ft.  
thence S 26° 30' W. 434.0 ft. thence N 78° 41' W. 153.1  
ft. to a point W. 22° 44' E. 465.6 ft. from place of  
beg. thence S 22° 44' W. 465.6 ft. to beg. 10.58 a.

Dec. 4 - '02  
survey of 20th Street.  
See also page 73 - this  
book.



See page 73  
this book  
See also Book  
L-193

Continuation  
page 102.

S.E. 1/4 of N. 1/4 of Sec. 23, T. 7. N. R. 2. W.  
Fence on N. Side of Street  
Fence on S. Line of Str.