

Traverse table of boundary line of tract to be conveyed by C.F. Wade to J.M. Wade in W/4 of Sec 7 T. 7. N. R. 1. E. Feb 18 - 1903. (See plat Book - page 133.) Req. 134.5.2 ft. S. of N. W. cor. of said Sec. in Cobble Creek bed. N. R. 1. E. sec also page 100 - this book.)

| Course      | Dist   | N.    | Lat | S      | + E.  | Dep    | - W | Lat     | Dep    | D.M.D.  | + (double courses) |
|-------------|--------|-------|-----|--------|-------|--------|-----|---------|--------|---------|--------------------|
| 588° 10' E  | 724.4  |       |     | 23.2   | 724.0 |        |     | -23.2   | +724.0 | +724.0  | 16 796.80          |
| 581° 26' E  | 578.1  |       |     | 26.1   | 571.6 |        |     | -26.1   | +571.4 | +2019.4 | 173 470.34         |
| S 0° 20' W  | 1854.1 |       |     |        |       | 18.5   |     | -1854.2 | -10.5  | +2580.3 | 4 784 392.26       |
| 573° 21' W  | 352.5  |       |     | 72.3   |       | 241.9  |     | -72.3   | -242.0 | +2327.8 | 168 299.94         |
| N 25° 58' W | 831.7  | 77.7  |     |        |       | 364.1  |     | +77.7   | -364.1 | +1721.7 | 1287 315.09        |
| N 63° 36' W | 787.9  | 327.0 |     |        |       | 678.8  |     | +327.0  | -678.8 | +678.8  | 228 785.60         |
| N           | 951.1  |       |     |        |       |        |     |         |        | +951.1  |                    |
|             | 2035.8 |       |     | 2035.7 |       | 1295.6 |     |         |        | 1295.3  | 1516 070.69        |

19 Description of tract to be conveyed by C.F. Wade to J.M. Wade  
 Pt of Sec 7, N.W. 1/4 Sec. 7, T. 7, N. R. 1, E. S. 1/4 N. Beg at point on Sec. line 134.5.2 ft. S. from the N.W. cor. of the said Sec. running thence 588° 10' E 724.4 ft. - S 0° 20' E 1854.1 ft. - S 0° 20' W 1854.1 ft. - 573° 21' W 352.5 ft. - N 25° 58' W 831.7 ft. to 1/4 Sec. line. - N 63° 36' W 757.9 ft. to a point on Sec. line 383.7 ft. N. from S.W. cor. of N.W. 1/4 of said Sec. thence N. 951.1 ft. along the Sec. line to beg. ~~44.3 acres~~ 37.27 acres

16-14 James A. Herrick to Susan W. Herricks Feb. 28 - Mar 1 - 1903.  
 Pt. S.E. 1/4 Sec. 5, T. 5, N. R. 1, W. Beg. 21.36 ch N. + 17.42 ch W. of S.E. cor. ad 1/4 Sec. W. 1.22 ch - N 42° 21.22 ch - S 4.12 ch. to beg.

21-116 Conveys to Herricks heirs - same tract as described on my Survey - of S.E. 1/4 Sec. 5 - T. 5, N. R. 1, W. on blue print.

32-6 Susan G. Buford to Alex. L. Brewer - Pt. S.E. 1/4 Sec 5 - T. 5, N. R. 1, W. Beg. 18.11 ch N + 23.42 ch W. from S.E. cor. of said 1/4 Sec. - W 2.00 ch - N 2.50 ch - S 2.00 ch - E 2.00 ch - S 2.50 ch to beg. together with pt of Sec 7 Beg. 1360.26 ft. N. 0° 32' E. + 1547.22 ft. W. from S.E. cor. of said 1/4 Sec. - N 0° 58' E. 66.76 - W 15.81 ft. to a point 33.86 E. of center of young str. or Grant Ave. - N 0° 58' E 260.7 ft. par. to Dept. line of said Ave. - W 66.76 - S 0° 58' W 260.7 ft. par. to S.W. St. W. 50.19 ft. - S 0° 58' W. 66.76. E. 152.86 ft. to beg. same being N. of and adjoining the road to S. of said

10-383 E. J. Herrick to Susan Buford same as 32-6

2-64 L. J. Herrick to Ludlow Bowen - Pt. S.E. 1/4 Sec 5 - T. 5, N. R. 1, W. Beg. 18.11 ch N. + 23.42 ch W. of S.E. cor. - W. 2.00 ch - N 2.50 ch - S 2.00 ch - E 2.00 ch to beg. with pt of W. drainage 32-6

2-336 L. J. Herrick to Sarah E. Randall Mar. 14 - 1889 - Pt. S.E. 1/4 Sec 5 - T. 5, N. R. 1, W. Beg. 18.11 ch N. + 19.42 ch W. of S.E. cor. of 1/4 Sec. - W. 2.00 ch - N 2.50 ch - E 2.00 ch - S 2.50 ch to beg.

9-101 L. J. Herrick to Sam. Herrick same as 12-12 - see blue print.

10-382 W. Buford & wife to L. J. Herrick - Pt. S.E. 1/4 Sec 5 - T. 5, N. R. 1, W. same as 32-6 in a general way, a pt of way. 66.76 ft. wide along N. side on line of Grant Ave & along full width of track 34 ft.

10-542 Francis Herrick wife to L. J. Herrick - Pt. S.E. 1/4 Sec 5 - T. 5, N. R. 1, W. Beg. 18.11 ch N. + 21.42 ch W. from S.E. cor. 1/4 - W. 2.00 ch - N 2.50 ch - E 2.00 ch - S 2.50 ch to beg. 1/4

12-11 Sarah E. Randall to L. J. Herrick - Beg. 18.11 ch N. + 19.42 ch W. from S.E. cor. 1/4 - W. 2.00 ch - N 2.50 ch - E 2.00 ch - S 2.50 ch to beg.

12-12 Sam. Herrick to L. J. Herrick Pt. Same 1/4 Sec. Beg. 18.11 ch N. + 17.42 ch W. of S.E. cor. 1/4 - W. 2.00 ch - N 2.50 ch - E 2.00 ch - S 2.50 ch to beg.

12-48 L. J. Herrick to Henry E. Gould - Beg. 18.11 ch N. and 17.42 ch W. of S.E. cor. 1/4 W. 4.00 ch. - N 2.50 ch - E. 4.00 ch. - S 2.50 ch. to beg. also Pt. Beg. 20.61 ch. N. + 17.42 ch. W. of S.E. cor. 1/4 - N. 50. ft. - W. 41.81 ft. to pt 33 ft. E. of Grant Ave. - N. 0° 58' E 276.7 ft. par. to said Ave - W. 66. ft. - S 0° 58' W. 276.7 ft. - W. 50.19 ft. - S 52.8 ft. to beg.

13-575 L. J. Herrick to Henry E. Gould - Pt. S.E. 1/4 Sec 5 - Beg. 18.11 ch N. + 17.42 ch W. of S.E. cor. 1/4 - W. 4.00 ch. - N 2.50 ch. - E. 4.00 ch. - S 2.50 ch. to beg. also Pt. Beg. 20.61 ch. N. + 17.42 ch. W. of S.E. cor. 1/4 - N. 50. ft. - W. 41.81 ft. to pt 33 ft. E. of Grant Ave. - N. 0° 58' E 276.7 ft. par. to said Ave - W. 66. ft. - S 0° 58' W. 276.7 ft. - W. 50.19 ft. - S 52.8 ft. to beg.