

70

Note Block 6 Plat "a"  
Ogden City Survey -

A wooden stake (pine) about 16" long with a nail in top is driven into the ground near S. W. corner of said Block

7.5 feet West <sup>and</sup> 9 feet South from said S. W. corner of Block 6 - being at Right angle with Main Street,

Done - April 22 - 1889  
in setting corner for Mrs. Thomas.

Note

On 8th Street at intersection with Spring a large rock is set into the earth about 1 1/2 ft and a point taken on top - and another smaller stone is placed on top of said rock and a point taken on it and the earth placed over it and rammed in tight. about 4 inches of earth placed over all -

The rock is 1.5 ft too far North for the center of 8th Street but is precisely in the center of Spring Street -

Block 3 - Plat "a" O.C.S. is precisely 5 feet to large East and West on 8th Street.

Done April 9 - 1  
in setting Mrs. Evans Corners.