

Commencing at a point being the N.E. cor,  
the 2nd bridge over the Weber River,  
in Weber Cañon about 9 miles N.E. from  
2000 Summit Co. Utah, thence West  
~~and West~~ from said bridges 160 Rods  
South 160 Rods, East 320 Rods North  
60 Rods West 160 Rods to place of  
Cry. containy 320 acres

Case of J. C. Dolan & Cannon set for April 15-1899

N. on line bet 19-24 T 6 N R  
W & E

7.50 Ch ente Cold W. canon drains N.W.  
1.70 Spring branch 10 links into 7" deep N.W.  
1.50 Road bears N.W. & S.E.,  
5.00 ascend.

Top of ridge N.E. & W set a limestone 14x10  
9" in ground for 1/4 cor. Mark for S.L.M.  
on W. face & raised Stone Mound along side  
descend.

5.59 Post 4, lot 38 "Little Harry" mining claim  
bears N 54° 15' E, 93 links dist

8.01 same post bears S 22° E, 202 ch.

4.00 Mouth of gulch heads S.E. house W 500 ch.

7.39 E side Road Ogden Cany N.E. & S.W. marked  
a boulder, 2x1x1' above ground for W.C.,  
to See 13-18-24-19 3 notches on S.W. edge  
W.C. & S.L.M. building, of which lot  
bears W 600

38 S. side Ogden Riv 8' deep, 12.5' wide S.W.  
It being impossible to chain further on  
set River & perpendicular rocks  
a flag was set on top of ridge & find  
dist to be 23.00 ch by triangulation