

174

Base line ✓

T1N R6 E. =

E. on true line along the South
boundary of Sec 36 -Ver $16^{\circ}49'E$.

ch

40.

Set a ^{Wagon Boulder} boulder rock 18" long
14" wide 13" thick 10" in ground
& marked $1/4 S$ for $1/4$ Sec

80.00

Set a sandstone 16" long 14" wide
8 inches thick 10" in the ground
for cor to Townships 1 N. Ranges
6 and 7 East, raised a mound
of stones 20" high 24" diam
Cor. stone notched 6 notches to W
6 notches to N, and 6 notches to East
land broken - mountainous
Soil 3rd rate - timber scattering
aspens.Registered in Field Book
10 - Page 10 -

✓

Copy of deed from John Taylor to Reese J. and James P.

Heminger - dated Oct. 17-1892 - Recorded at book P -

page 385 - Part of the $1/2$ Sec 27 T7N R1E,Bsq. N.E. cor. said $1/2$ Sec. thence N. 25.50 ch, $S12^{\circ}45'W$ 41.00 ch, W. 5.50 ch, to Sec. line, S 38.60 ch, $N56^{\circ}E$ 34.20 ch, $N24^{\circ}12'W$, 22.25 ch, $N41^{\circ}14'E$ 2.55 ch, $N69^{\circ}E$ 17.00 ch, to E. line of said $1/2$, $N36.45$ ch to by

205.81 =

✓

Copy of deed from N. Turner to Burch Creek

Land & Water Co. Part of N.W. $1/4$ Sec. 4T5N R1W. Beg. 20. ch S. N.W. cor. $1/4$ - S. 13.50 $S45^{\circ}E$. 16point. 6.50 ch. E. from S.W. cor. $1/4$ E 7.75 N. 30. ch W. 9.25 S. 10