

Salt Lake Base line - Copy of field 175
Notes in Surveyor General's office at
Salt Lake City. Copied April 18-1888 -

chains L. 1 N R. 6 - East of the Salt Lake
meridian -

East on a true line along the South
boundary of Section 32 -
Ver $16^{\circ}42'E$,

1.00 Dry hollow - descending South East
4.10 Small spring branch in a deep hollow
heads about 50. ch N. of line and runs
South

0.00 Set a pine post 4 ft long 4 inches dia
12" in ground for $\frac{1}{4}$ Sec Cor. from which
an aspen 8" diam bears S 14 links
distant. An aspen 10" diam bears
North 8 links distant. Aspen 8" dia
bears N $45^{\circ}W$ 8 lbs dist and marked
B A S E

0.00 Set a sandstone 18" long 8" wide 5" thick
13" in the ground for cor to Sec 32-33
marked 2 notches to W & 4 notches to E.
land - foothills, high mountain 60 to 100
ch to north - timber scattering - aspen
& pine

Registered in Field Book
No 10 - Page 7 -

4.00 ch East along a true line on the
S. boundary of Sec 33 - Ver $16^{\circ}45'E$,
Enter head of a deep dry hollow
descending S.W.

40. Set a sandstone 15" long 7 1/2" wide
6" thick 10" in ground for $\frac{1}{4}$ Sec Cor.

1.00 Leads dry hollow

8.50 Top of a ridge - S -