

S. L. City June 3-1892 - Copy of Notes of
U. S. M. M. No 2, Paradise Mine dist.
cutting about 200 ft. westerly from and about
same dist. vertically above the bottom of
La Platte Gulch draining N.W. 1
consists of pine post 6" square, 8 ft long set 3'
in ground - marked U. S. M. M. No 2 & the lines
of letters filled with nails 1/2 in apart
From M. M. No 2, the N.E. cor of Boarding house
in La Platte town bears S 28° E & the
centre of La Platte Mine shaft bears S 75° 36' E
1341 ft actual measurement - N.W. cor Sullivan
Cabin, the most northerly ^{down} cabin in La Platte
town bears S 65° E 357 ft. actual measurement
a pine 10" diam bears S 40° W. 48 ft
a pine 2' diam bears S 32° E 54 ft both trees
were blazed 2 ft above the ground and
marked - U. S. B. T. M. M. No 2,

Cor to Sec 12-13 on E. boundary T. 8. N. R. 2 E
bears S 69° 41' E 7000.0 ft actual measurement
this being the western cor to the Public
Survey that could be found after diligent
search (after)

The true meridian to which all courses herein
are referred was determined by an observation
on Polaris at its Eastern elongation, made
at a point near the La Platte Boarding house and in
sight of M. M. No 2 on the evening of Oct 7-1891 -
at 6-19 o'clock mean Solar time the mountain
standard time of the observation was 6-45. Transit
set over peg A, directed to Polaris - peg driven