

on line about 50 yds dist Angle at A bet. Peg  
 B - and a flag U. S. M. M. N<sup>o</sup> 2 read  
 40.°00' which after deducting the azimuth angle  
 for the year 1891 - in Lat 41.° W North showed the  
 true bearing of the initial line to be 738°19' W  
 and from this all other lines ~~was~~ of the survey were  
 turned by plate angles.

Mean Magnetic Var 17°30' E

Established U. S. M. M. N<sup>o</sup> 2 Oct 8-1891 -

Robert Gorlinski

Note from Post 1 of Superior Lode the N.W. cor of  
 Sullivan's Cabin or house 12 x 5 ft the most  
 northerly house in La Plata town bears 578°35'E  
 220. ft the town of La Plata lies entirely  
 S. E. th. therefrom.

General Description, the Sunrise - the conflicting  
 claim is the Sundown location not officially  
 surveyed on the S.W. cor of the claim, there  
 is no conflicting or adjoining claim surveyed  
 for U. S. Patent. - the adjoining locations  
 are the Mountain Bay & Glenco,