

Beq. 2 1/2 r. E. of S. W. cor. Lot 1. Bl. P.B. N 80  
E 2 1/2 r. S 8 r W 2 1/2 r. to Cug.

18-270 Francis Robinson & wife & Julia S. Chapple  
to Annie E. Moore. Aug 1-1892. 1700.

Beq. 17 1/2 r N. of S. E. Cor. Lot 1. N 5 1/2 r. W 2 1/2  
S 5 1/2 r. E 2 1/2 r. to Beq, sub. to rt of way 10.  
wide along W. side Aug 2-1892

18-299 Francis Robinson to Julia S. Chapple  
July 30-1892. 200. Pt Lot 1. Bl. P.A. 100

Beq. 17 1/2 r N. of N. E. Cor. W 2 1/2 r. S 2 1/2 r  
E 2 1/2 r. N 2 1/2 r. to Cug, with R of W. 10 ft  
wide along W. side of Lot 1.

Bearing trees. to Block Corners & c. in Pebble  
Park. shown on page 133, Surveyed July  
1893, Lee Curtis, H. Newman Chain

N. W. Cor. Block. 2. Marked by 2"x2"x2 ft stake &

tree joints in Pebble Park.

15" in ground from which a cottonwood tree 8" diam. blazed  
2 ft. above ground bears S 32° 55' E 27.05 ft dist. a cotton  
tree 8" diam. blazed 4 ft above ground, starting on N.  
of Hooper Canal bears S 29° 10' W. 47.5 ft distant.

A cottonwood tree 12" diam blazed 2' above ground bears  
49° 10' W. 4.5 ft distant - Benlmond Peak bears  
N 9° 40' E. true course. - N. line of Block N 2 2,  
bears N 89° 23' E. the W. line B 2. bears 30° 4'  
from N. W. cor. B 2. The N. line of "Sec. bears N 0° 4'  
530 ft distant to a point 1319.6 ft. S 39° 23' W. from  
N. E. cor. S. E 1/4 Sec. 30. T. 6. N. R. 1. W.

N. E. Cor. B 2 2"x2"x2 ft Stake 15" in ground from which a blazed  
cottonwood tree bears 665° 50' E 31.4 ft. a cottonwood tree 5" diam  
N 17° E 26.8 ft.