

(Field-notes) JAN. 25th 1895.

S. I. City

T. H. N. - R. S. W. Book N^o 70, Pages 148. (Original)

I. bet Secs 17-20. Random 53.⁰⁰ prof. crushed Wt. 55.60 chs Blueberry & 77.80 1/2 part cor. Sec. 16-17. W. on true line. 39.90 1/4 Sec. part, mid & pits.

E bet Secs 20-29. Random. 32.⁴⁰ Blue Spring cr. 79.78 chs. cor. to Sec. 20-21-28-29 W. on true line. 39.89 1/4 Sec. part Mid of earth & pits

W. bet 19-30. Random. 80.17 ch. to post cor. to Sec. 19-30. on W. side. T. H. N. S. W. E. on true line. 40.08 set 1/4 Sec. part, mid of earth & pits

N. bet 19-20. 40. ch bet 1/4 Sec. part mid & pits 54. 2 wash break of Mt. 80. bet part cor. to sec 17-18-19-20. N. bet 28-29. 40. ch bet 1/4 part mid & pits 80. ch bet part cor to 20-21-28-29

W. bet 30-31. on random 80.10 ch to part cor. 39-31 on W. side. T. H. N. S. W. E. on true line 40.05 set 1/4 part mid & pits. June-1856-

N. bet 30-29. 40. ch 1/4 part, mid & pits 80. bet part cor to 19-20-29-30.

E bet 29-32. Random 18.35 Blue sp. crack 15 lbs cor 77.84 part cor. to Sec. 28-29-31-32 W. on true line 39.92 set 1/4 part mid & pits

T. H. N. - R. S. W., (Notes) Book A-214 page 553, (Re-survey.)

N. on re-survey line bet 19-20. Var. 18-20' E. over flat. 17.⁰⁰ ch Wash. Brains N.E. 40. ch leave flat brass N.E. & S.W. no trace of old cor.

Set sand stone 12" x 10" x 8. 8 in. in ground. In re-est. 1/4 cor. marked from W. face. pits unproductive

40.90 fence N.E. & S.W.

41.36. Tel poles N.E. & S.W. 41.95 Central post

Ry. N.E. & S.W. 43.13 fence N.E. & S.W.

43.40 poles. 80. no trace. est. re-survey

lime stone 20" x 12" x 10" 15" in ground cor to 17-18-19-20

E. on random-re-survey bet 17-20. Var 18-40' E

40. bet tramp cor. 79.80 intersect N & S. line

30 lbs S. of cor. to Secs 16-17-20-21. these

2 km. 589-47' W. on true line re-survey line bet

17-20 same Var 70. enter flat brass N & S

39. ch road N & S E. 39.90 no trace of old cor

bet re-survey cor. lime stone 18 x 12 x 9 / 2, in

ground for re-estab cor. 44.⁵⁰ Blue area

20 lbs wide 18" deep. S.W.