

JAN-25-1895.

O.I. City

47. enter mountain bears NE & S.W. 79.80 cor to Sec. 17-18-19-20

589°-52' W on true re-survey line bet 20-29. Va. 18°-42'

15. ch. wash drains S.W. 39.87 set round stone 10" X 10" X 10" 6" in ground for re-survey cor. 14 cor. Md. 12 on N. face, (mid of stone) pile impossibly from

with tel. section - corner bears S 39°-30' W. about 4. ch dist. Bunk House S. 70° W. about 3.52 ch.

46.50 lineal NW & SE 48.70 fence NW & S.E 48.70 pole

49.55 C.P.R.R. NW & S.E 30.25 poles 50.50 gate

57. Blair Cr. 10-lks wide 18" deep. 79.78 cor. to 19-20-29-30. Apr. 7-1887.

1189-49'E on true re-survey line bet 19-30. Va. 18°-42'

25. leave mt. enter flat NE & S.W. 27.40 fence 27.60 poles 28.50 C.P. RR NE & S.W. 29.20 poles 29.40 fence

40.17 set line stone 17x12x6. marked mid of stone 80.17 cor to Secs. 19-20-29-30

N. set 29-30 Va. 18°-20' 4.75 road N.E 30. wash S.E 40. set. limestone 20x12x7. 15" in the ground for re-set. 14 cor. 1/4 on W. face pile N & S.

80. set line stone 7x10x8 cor to 19-20-29-30

1189°-51'E on true line bet 30-31. re-survey Va. 18°-42'

11. fence 11.50 poles 12. C.P.R.R. NE & S.W. 12.55 poles 12.72 fence

40.10 enter gully set line-stone 19x14x6. 1/4 on N. face mid of stone. 47.50 road NE & S.W. 70x50 Road

80.10. cor to Secs 29. 30-31-32

589°-41' W on true re-survey line bet 29-32 Va. 18°-42'

10. water pipe NW & SE. 13. road N.W. 14. fence 14.25 poles. 15. C.P.R.R. 16. poles. 15.25 fence 39.92

set limestone 16x12x5. 1/4 on N. face pile S & W.

mid earth alongside 41.75 Blair Cr. 20 lks wide 2. ft deep. 54.50 wash drains S.W. 79.54 cor to Secs. 29-30-31-32

80.14 N 89°-51'E

79.54

