

Thence  $N 36^{\circ} 11' E$ .  
 along the northwesterly end line of this claim, descending,  
 centre of "Bear Gulch Creek" draining northerly,  
 centre of wagon road leading from La Plata town to Iogaru, in a northerly curve,  
 begin to ascend the east side of the gulch,  
 Set a pine post  $4" \times 4" \times 4$  ft. long, 12" in the ground and mound of stones 2 ft.  
 high and 4 ft. base, and marked the same U.S. 40. P. 3. for corner.  $N 23^{\circ}$   
 whence the most northerly to catcon post of this claim, found standing  
 in place bears  $N 36^{\circ} 11' E$ . 50 ft. distant. A pine stump 3 ft. high, blazed 2 ft.  
 above ground and marked 40. P. 3. and on a blaze 1 ft. above ground marked  
 B.T. bears  $N 34^{\circ} 29' E$ . An aspen tree 6" diam, blazed 2 ft. above ground and  
 marked 40. P. 3. and on a blaze 1 ft. above ground marked B.T. bears  
 $N 7^{\circ} 30' W$ . 57 ft. The centre of the mouth of the Alma Tunnel, bears  $N 53^{\circ} W$ .  
 122 ft. dist. with actual measurement. The centre of the mouth of the Red Jacket  
Tunnel bears  $N 83^{\circ} 06' W$ . 193 ft. distant, actual measurement.

340.  
370.  
380.  
595.6

Thence  $S 48^{\circ} 59' E$ .  
 along the easterly side line of the claim, ascending,  
 top of ridge, bearing northerly and southerly, thence descending,  
 intersect the Quarter Section line 242.75 ft.  $N 89^{\circ} 50' W$ . from the  
 Quarter Section corner on the east line of Sec. 11. Tp. 8 N. R. 2 E. by calculate  
 Set a pine post  $4" \times 4" \times 4$  ft. long, 12" in the ground and mound of stones,  
 2 ft. high and 4 ft. base, and marked the same U.S. 40. P. 4. for corner  
 $N 9^{\circ} 4'$ . which is identical with the most easterly location post.  
 of this claim, found standing in place. A pine tree 30" diam, blazed  
 2 ft. above ground and marked 40. P. 4. and on a blaze 1 ft. above ground  
 marked B.T. bears  $N 18^{\circ} E$ . 18 ft. A pine tree 24" diam, blazed 2 ft.  
 above ground and marked 40. P. 4. and on a blaze 1 ft. above ground  
 marked B.T. bears  $S 80^{\circ} E$ . 107 ft.

500.  
1183.64  
1483.2

Thence  $S 36^{\circ} 11' W$ .  
 along the southerly end line of the claim, descending.  
 centre of wagon road leading westerly to La Plata town, thence ascending  
 Post 1. of this claim, the place of beginning

529.  
591.6

Description of the boundaries and corners of the  
RED JACKET LODE.

Beginning at the identical place of discovery where a notice is  
 posted, identified by affidavit's filed herewith, I set a pine post  
 $4" \times 4" \times 4$  ft. long firmly in the ground and mound of stones 2 ft.  
 high and 4 ft. base, and marked the same U.S. Lot 40. D's.  
 From this point a pine tree 15" diam blazed 2 ft. above ground  
 and marked D's. 40. and on a blaze 1 ft. above ground marked  
 B.T. bears  $N 48^{\circ} 10' E$ . 33.8 ft. A pine tree 8" diam, blazed 2 ft. above  
 ground and marked D's. 40. and on a blaze 1 ft. above ground  
 marked B.T. bears  $N 73^{\circ} 30' E$ . 40 ft. From this discovery post,  
 a shaft 6 x 6 ft. square and 7 ft. deep, bears  $S 58^{\circ} 58' E$ . 15 ft. distant.  
 The east gable of J.P. Law's store in La Plata bears and Post Office  
 building in La Plata, bears  $S 19^{\circ} 35' E$ .

2.4 Ft  
2.3.25  
219.75

Thence I run  $N 36^{\circ} H E$   
 to the centre of the vein.  
 Thence I run  $N 28^{\circ} 56' W$ .  
 along the centre of the vein,  
 to the Northwesterly end line of the claim,  
 Thence I run  $S 28^{\circ} 56' E$ ,  
 along the centre of the vein,  
 to the south-easterly end line of this claim, and to the North-  
 westerly end line of the Queen of the Hills Lode.

296.7

Thence  $S 36^{\circ} 11' W$ ,  
 along the south-easterly end line of this claim, and along the  
 north-westerly end line of the Queen of the Hills claim,  
 Post 2. of the Queen of the Hills claim, which is identical with  
 the most southerly location post of this claim; I therefore  
 mark this post on its northerly face U.S. L. 40. P. 5. for corner  
 $N 0^{\circ} 5'$ . A pine tree 8" diam, blazed 2 ft. above ground and marked  
 40. P. 2. and on a blaze 1 ft. above ground marked B.T. bears  $S 10^{\circ} W$   
 29.6 ft. A pine tree 8" diam, blazed 2 ft. above ground and marked  
 40. P. 2. and on a blaze 1 ft. above ground marked B.T. bears  $S 32^{\circ} 20' E$   
 28.7 ft.