

Thence N 28° 56' W

468.7

along the south-westerly side line of the claim, ascending the west side and intersect the south side line of the Mountain Boy Lode Lot 39, S 89° 09' W. 423.9 ft. from Post 4. of Lot 39, by actual measurement, and N 89° 09' E 11.1 ft. from Post 2. of the Sunrise Lode, Lot 38, by actual measurement. This point is on the summit of the ridge bearing north-easterly and south-westerly; thence begin to descend,

1173.96

intersect the south side line of the "Lorette" Lode, Lot 39, N 89° 42' W. 605.24 ft. from Post 3. of said Lot 39, by actual measurement, and S 89° 42' E 752.96 ft. from Post 2. of said Lot by actual measurement.

1219.75

Set a pine post 4" x 4" x 4 ft. long 12" in the ground and mound of stones 2 ft. high and 4 ft. base, and marked the same U.S. 40, P. 6, for corner No 6, which is identical with the position of the most westerly location post of this claim found standing in place. A pine tree 20" diam. blazed 2 ft. above ground and marked 40, P. 6, and on a blaze 1 ft. above ground marked B.T. bears S 69° W 3 ft. A pine tree 15" diam. blazed 2 ft. above ground and marked 40, P. 6, and on a blaze 1 ft. above ground marked B.T. bears S 34° E. 17.5 ft.

The local variation of the needle at this point is 172° 30' E.

Thence N 38° 11' E.

515.5

along the north-westerly end line of the claim, at right angles to slope of. Set an aspen post 4" x 4" x 4 ft. long, 12" in the ground and mound of earth 2 ft. high and 4 ft. base, and marked the same W.C. 40, P. 7, for witness to corner No 7, which is liable to be washed away by Spring freshets,

525.3

Set an aspen post 4" x 4" x 4 ft. long 12" in the ground, and in the south edge of Bear Gulch Creek, and marked the same U.S. 40, P. 7, for corner No 7, whence the most northerly location post of this claim found standing in place bears N 32° W 48.3 ft distant. A cottonwood stump 3 ft. high and 4" in diam., blazed 2 ft. above ground and marked 40-P. 7, and on a blaze 1 ft. above ground marked B.T. bears N 46° E 17.3 ft. An aspen tree 6" diam., blazed 2 ft. above ground and marked 40, P. 7, and on a blaze 1 ft. above ground marked B.T. bears N. 80° E 9 ft.

Thence S 32° 00' E.

27.2

along the north-easterly side line of the claim. Set an aspen post 4" x 4" x 4 ft. long 12" in the ground and mound of earth 2 ft. high and 4 ft. base and marked the same W.C. 40, P. 7, for witness to corner No 7; thence ascending.

550.79

intersect the south side line of the "Lorette" Lode Lot 39, N 89° 42' W. 25.5 ft. from Post 3. of said Lot. by actual measurement, and S 89° 42' E. 1332.9 ft from Post 2. of said Lot. by actual measurement. This point is on the summit of the ridge, thence begin to descend,

897.53

intersect the East end line of the "Mountain Boy" Lode Lot 39, S 0° 16' E 288.08 ft. from post 3. of said Lot by actual measurement and N 0° 16' W. 313.92 ft. from Post 4. of said Lot by actual measurement.

950

centre of Bear Gulch Creek, draining north-easterly; thence ascending centre of wagon road from La Plata town to Logan bearing north-easterly corner No 3 of the "Queen of the Hills" Lode. This Post being identical with the easterly corner of this claim, I mark on its west face U.S. 40, P. 8, for corner No 18; whence the most easterly location post of this Field Jacket Lode, bears N 36° 11' E. 50 ft. distant.

979

A pine stump 3 ft. high, 20" diam. blazed 2 ft. above ground and marked 40, P. 3, and on a blaze 1 ft. above ground marked B.T. bears N. 34° W. 29 ft. An aspen tree 6" diam. blazed 2 ft. above ground and marked 40, P. 3, and on a blaze 1 ft. above ground marked B.T. bears N. 72° 30' W. 57 ft. The centre of the mouth of the Alma tunnel bears N 53° W 122 ft. distant, actual measurement, the centre of the mouth of the Red Jacket tunnel, bears N 83° 06' W. 193 ft distant, actual measurement.

1192.1

Thence S 36° 11' W.

along the southeasterly end line of this claim and along the north-westerly end line of the "Queen of the Hills", descending.

216.6

225.6

255.6

595.6

foot of hill, centre of wagon road from La Plata to Logan bearing north-easterly, centre of Bear Gulch Creek, draining northerly; thence ascend the hill, Post 5. of this claim the place of beginning.