

therefore run N 6° 07' W, and S 89° 53' W, according to this
last line.

Mar 23rd 1895

From the cor. to Secs 8-9-16-17, T. 4 S. R. 1 W.
N 69° 23' E to smoke stack of Agency Mill, N 17° 45' E
N 74° 48' W to S. Crum, Episcopal Mission Bldg.
Thence Iron S 20 chs west cor. 40 chs set 1/2 way to west
1/16 cor. to chs set cor to Sec. 16-17 Thence Iron S
20 chs and find cor. set by Brown 36. line to south.
Thence Iron S 20 chs & find corners cor 10 chs west, thence
From Browns Cor, Iron N 88° 58' W, 20 chs find 1/16 sec. cor.
in west side of quercus. From S. E. Cor. of S. N. 1/2 of S. N. 1/4 Sec. 16, Iron
N. 80 chs. & find 1/16 cor. to bank E.

Tuesday

March 25-1895

From the cor. to Secs 1-2-11-12, T. 4 S. R. 1 W. which is a stone, with
pits & mound. Estab. Mar. 22. From Nashakce tank bearing N 76° 45' W.
Iron West 20 chs set 1/16 cor. 40 chs set 1/2 cor. to chs set 1/16 cor. 30,
chs west cor. to Secs. 2-3-10-11, not finding the reg. cor. from which
spire on school bears N 30° 18' W. tank bears N 68° 58' W.

From the cor. to Secs. 2-3-10-11, Iron N. 20 chs. from which spire on
school bears 74° 15' E. 40^{1/2} chs from the school 58 chs North
60¹⁰ find 1/16 cor. 65 chs W. firmly in ground. 30.45 find
cor. to Secs. 3-4-9-10, 68. links N. of my line.
From this sec. cor. which is not buried, side tank at T.C. Nashakce
bears. N 43° 29' W. spire on school bears N 80° 53' E
from this find that may bear the sec. line must bears 78° 45' W
From the cor. to Secs 3-4-9-10, Iron S, 80¹⁰ chs find Sec.
stone, 27 chs West of my line. This Sec. line therefore bears
S 0° 11' W. From the cor. to Secs 9-12-15-16, N. 80° 53' E
spire on school bears N 38° 01' E. from this cor,
the S. line of Sec. 16, bears N 82° 48' W

From N.E. Cor. of S.E. 1/4 of S.E. 1/4 16, Tank bears 77° 24' W
Agcy founds side of bears 77° 40' W. abt. 1/2 dist.
E.gable of Jones Bldg, bears N 48° 52' W,
From the 1/4 sec. cor. from the true line bet Sec. 9-10, Tank bears
77° 27' W. E.gable Jones Bldg, bears S, 39° 00' W. Spire on school
bears N 53° 53' E. From 1/4 cor. on line bet 9-10, Iron N 89° 45' W,
along 1/4 sec. line, 20 chs set stone for 1/16 cor. mound & pits 8 & 20,
from which, E.gable of Jones Bldg, bears, S 41° 13' E, tank bears
N 75° 55' W, thence Iron S 2° 11' W. 40 chs. The N. N. cor
the Mexican Bldg bears S 78° 20' E abt. 1/2 chs. dist. at 15 chs. set
stone, with pits & mound
from which the tank bears N 13° 39' W. (3 1/2 miles)

T. 3 R. 1 E March 26th 1895.

From the cor. to Secs 19-20-29 & 30, which is a stone marked
5 notches on E. & 2 notches on S. pits & mound. Iron N 10° 37' W,
on random line, at 20 chs. find 1/16 cor. 21 lbs. E. at 40 chs. find 1/4
cor. stone firmly in ground. 143. link East. From the 1/16 cor 20,
chs. N. of Cor. to Secs 19-20-29-30, Iron line to 20³ chs. find 1/16 cor.
27 lbs. South firmly set. thence from this 1/16 cor. Iron S. 20,
chs. find old 1/16 sec. stone 12 lbs W. at 40.4 chs. find 1/16 stone
firmly in ground 40 lbs west. thence from find 1/16 cor. Iron N.
at 20. chs find 1/16 cor. stone firmly in ground 29. links North. 40. chs find
1/16 cor. stone firmly in ground 18 links North. thence from this 1/16 cor.
Iron N. 20. chs find 1/16 sec. stone firmly in ground 31. links E. 40 chs
find 1/16 cor. 3
takes on line?

From the cor. set. on Sec. line bet Secs N 9° 16' T. 1 S. R. 1 W.
10. chs. S 90° 16' W. of 1/4 cor. Iron S 89° 45' E 20 chs and set
cor. thence Iron N 0° 11' E 10. chs. set. cor. thence Iron
S 0° 11' W. 20. 10 chs. & set. tab. 1/16 cor. from which N.E. cor. bears