

bears N. 79° 27' W, about 7.00 chs. The N. W. cor of Meesters  
 bears N 89° 55' W, about 7.00 chs. dist - tank bears N 30° 25' W, from  
 Thence I ran S 89° 45' E, 20. chs. & set 1/4 cor. from which chain on  
 school bears N 85° 40' 45" tank bears N 38° 05' W. Thence I ran  
 0° 11' N, 20. chs. and the 1/4 cor. firmly in ground 10 links N. Thence  
 I find this tank bears S 60° 26' E, from this 1/4 Sec. cor.  
 from S 0° 06' E, 20. ch. & set 1/4 cor. above From the 1/4  
 cor. set Sec. 15 & 15, the Sec. cor. bears N 89° 42' W, The 1/4 cor.  
 on Rodgers Lane mission school bears N 54° 26' E (3 1/2 miles)

Wednesday March 27 - 1895

From 1/6 Sec. Cor. 20. chs. N. 21° E cor to Secs 9-10-15-16. T. 1, S. R. 1, W.  
 I ran S 89° 45' E, 10. chs. S 0° 21' W 20 ch to S. line Sec. 10. Thence  
 ran S 89° 45' E along 3/4 lin 15, 10 chs to old 1/4 Sec. Cor.  
 Thence I ran S. 0° 11' W 20. chs. set 1/4 cor. 40. 45 chs find old  
 firmly in ground 12 links E west from this cor. I ran S 89°  
 20. chs find old 1/6 cor. in line. Thence I ran N. 20. chs to 1/6  
 Thence I ran E 20. ch. & set 1/6 cor. Thence I ran N. 20. chs  
 S. line of sec 16. & set 1/6 cor. Thence Ran W. along Sec. line 20  
 chs to 1/4 cor. From the 1/4 Sec. cor. or 0° 06' W, 20. 14 to old  
 From the cor. to Secs. 3, 4, 9, 10 T. 1, S. R. 1, W. I ran  
 N 89° 45' W, 20. chs. no trace of old cor. I ran 1/6 cor. pit 64  
 40. 00 ch. and build trap 1/2 on 40. 33 find browns 1/6 cor. &  
 links S. 11th in ground. 60. 54 chs full 1/6 Sec. cor. by 170  
 85 links S. 30. 65 chs. find Sec. cor. cor. to Secs 4-5  
 and 9. 104 links South not in ground. Therefore the line  
 between Secs 4 & 9. bears S 89° 20' W, so found.  
 From the cor. to Secs 4-5-8-9, the tank bears, N 36° 24' E. Thence  
 from this Sec. cor. I ran N. 20. chs. set trap 1/6 cor. 40 chs  
 traps in 60. chs. set traps 1/6 cor. 30. ch. find browns  
 Sec. cor. 79 links North from the cor. to Secs 5-6-7-8.  
 from which, tank bears N 67° 24' E, the course of the  
 lat. Secs, 5 & 8, bears N 89° 25' W, (2 miles)

March 28 - 1895

Isotas comes on by's line between Secs 3 & 10. - 2 & 11,  
 T. 1, S. R. 1, W. from the temporary random corners set by  
 Oregon also at 1/6 cor. on the 1/4 Sec. line N 4 S. on N 1/4  
 31 - T. 1, N. R. 1, E. for Bill Friday. Thence ran E. 10 chs  
 set cor. 20. ch. found old cor. Thence from the 1/6 cor. above  
 named on N. 1/4 S. Sec. line. Ran W. 20. ch. & set 1/6  
 40. ch. set cor on W. Meridian. From which ran S. on  
 Meridian 20. chs. to 1/4 cor. From this 1/4 cor. I ran N. 40. ch  
 and found Sec. cor. firmly in ground, marked IIII on N. and I on  
 face M. C. on W. side. Long cor. to Secs 30-31-25 & 36. a  
 Mand. R. S. M. C. From which I ran N. 20. chs. and set  
 1/6 cor. above firmly in ground on S. bank of Sags Cr. drawing  
 Thence I ran E. 20. chs and do not find 1/6 cor. re-sets  
 with stone, pits 5 & 20. mound on N. side (4 miles)

Friday March 29<sup>th</sup> 1895

From the N.E. cor. of S. E. 1/4 S. W. 1/4 Sec. 30. T. 1, N. R. 1, E. I ran  
 S. 20. chs. & re-set old 1/6 cor. 40. chs. find 1/6 cor. from which  
 I ran E 20. chs. full 1/6 cor. from which I ran S 20. chs. & set  
 1/6 cor. 40 chs. estate. 1/6 cor. 60 chs. estate 1/6 cor. & find  
 on Barn on S. line of Sec 31, 20. chs. E of 1/4 Sec. cor. which  
 I find firmly bedded. (2 miles)

Saturday March 30 - 1895

In forenoon snowed some, work being interrupted therefore  
 I assisted in moving the belongings of Mrs. Clark,  
 afternoon, fair weather.

65 26527 F