

Sunday March 31-1895,
Day fair, no field-work done.

Monday April 1-1895.

From the Cor. to Sec. 27-28 33434, T. 1. N. R. 1. E. marked 1. or S. 43 on E. cor. by a line stone. Scribes 2. of found S.E. Backright on $\frac{1}{16}$ cor. 20. chs. W. of this Sec. Cor. I ran E. 20 links S. 27-434. Va 17-25, E. 80. chs. re-estab. $\frac{1}{16}$ cor. find old stone lying loose on ground. Next the same firmly, and dig pits N.E. & W. and mound on N. side 40. chs. re-est. $\frac{1}{16}$ Sec Stone which I find loose on ground. Pits E & W 4. ml on N. Hence I ran N 20. chs. and re-estab. $\frac{1}{16}$ cor. stone with pits 4 mound. Hence I ran W. 10. chs. set trap cor. Hence N. 70. chs. set trap cor. Hence I ran E 20. chs. from which Red's house (Crow Chief) runs N. 3. chs. dist. Hence I ran E. 10. chs. Re-est ab. cor. 3.12 chs. S. of S. bank of Little Wind river, and to the center of Sec. 27. From which I ran N. 20. chs. and set $\frac{1}{16}$ cor. stone, mound, 4 pits, Hence I ran W. 20. chs. & set $\frac{1}{16}$ cor. mound, 4 pits on S. side of Little Wind riv. From N.E. Cor. of N.W. 1/4 of S.W. 1/4 of Sec. 27. I ran N. 20. chs. set. $\frac{1}{16}$ cor. of (2. miles)

Tuesday April 2-1895.

From the cor. to Secs. 27-29 33434, T. 1. N. R. 1. E. from which Washlie & Needle bears N 24 20' W. I ran N. bet. Secs. 27-28, - re. chs. re-establish $\frac{1}{16}$ cor. Stone, mound 4 pits, 40. chs. re-establish $\frac{1}{16}$ cor. Stone, mound 4 pits, near wagon road, 60. chs. re-estab. $\frac{1}{16}$ cor. 80. thick brush, do not find Sec. Cor. 100. chs. find $\frac{1}{16}$ cor. 5 links E. on line bet. Secs. 21-22. From this cor. I ran E. 20. chs. find original cor. not in ground, 17. Links N. of my line. I re-estab. this cor. at the point where found with pits 4 mound, from which I ran N 20. chs. & set $\frac{1}{16}$ cor. 9 links E of line. re-establish this cor. at place found 7. links N. 4 S. build mound on W. side 40. chs. find $\frac{1}{16}$ cor. lying loose, 4 links W. which I re-establish at the place found, with pits 4 mound. From which I ran E. 20. chs. and find $\frac{1}{16}$ cor. 16. links S. firmly set in ground, I dig pits N 4 S. and build mound on N. side from which I run S. 20. chs. find old $\frac{1}{16}$ cor. on line which I re-establish with pits. N 4 S. mound N. 40. chs. find original $\frac{1}{16}$ cor. stone, on line 6, which I re-estab. pits N 4 S. mound W. 60. chs. find original $\frac{1}{16}$ cor. 7 links E. on the Sec. line bet. Secs 22 & 27. From which I run E. along Sec. line bet. Secs 22 & 27. 20. chs. re-estab. $\frac{1}{16}$ cor. mound N. 4 pits E & W. Hence I run S 20. chs. 20. chs. re-estab. $\frac{1}{16}$ cor. pits N 4 S. mound W.

3 miles

Wednesday April 3-1895

From S.E. Cor. S.W. 1/4 S.E. 1/4 Sec. 22, T. 1. N. R. 1. E. I ran N 20. chs. and estab. $\frac{1}{16}$ cor. 4 pits N 4 S. mound on W. side. From N. W. Cor. S.W. 1/4 of N.E. 1/4 of Sec. 22. above T.P. estab. yesterday, I ran E. 20 chs. and find old cor. stone 13. links N. do not change same but dig pits E & W. and build mound of earth on N. side 40. chs. find old $\frac{1}{16}$ stone 4. links N. I re-build corner at place discovery, pits 4 mound. From S.E. Cor. S.W. 1/4 S.E. 1/4 Sec. 22. I ran E 19. 82. chs. find Sec. Stone 33 links N. being the cor. to Secs. 22-23-26 and 27. 10. chs. and line marked 2 miles on E. and 2 miles on S. edges. From which I ran S 20. chs. & re-establish $\frac{1}{16}$ cor. From the N. Sec. Cor. on Sec. line bet. Secs 22-427. I ran S. 30. chs. & estab. cor. for Yellow Bull, on N. side river. From $\frac{1}{16}$ Sec. Cor. on line bet. Secs. 27 & 34, I ran E. 19. 30. chs. find old $\frac{1}{16}$ stone 40 links N. lying loose on ground. 20. chs. re-establish cor. 12. 75. E & W. mound on N. From $\frac{1}{16}$ Sec. Cor. on line bet. Secs. 27 & 34. I ran S. 20. chs. and re-establish $\frac{1}{16}$ cor. stone, mound on W. 4 pits N. 4 S.

3 1/2 miles