

stone lying loose, 39 links S. being cor to Sec. 17-18-19-20
 dig pits in each sec. and mound N. of Stone as found
 From which Ran W. 20 chs and find cor Stone firmly imbedded in the
 N. dig pits N.E. & S. of cor. & mid N. of stone as found. From which I ran
 789°-30 E. to the find old cor. 40 chs do not find cor. build same with
 pits N & S. mound N. From S.W. cor of N.W. 1/4 of N.E. 1/4 sec. 20
 Ran E. 20 ch.

(Driskell) Thursday April 11-1895.

From the cor to Secs 19 and 30, on the N. boundary
 of T. 1. S. R. 1. W. which is a limestone 8 X 10' firmly set in
 ground and pits N.E. - S.E. - S.W. - & N.W. I ran S. 40. ch find
 1/4 sec. Stone lying loose, marked, 80 ch find Sec. Stone
 120 chs. find old Sec. Stone 160. find S.W. cor. T. 1. S. R. 1. W.
 from which I ran S. 20 chs. & build 1/6 cor. mound N. & pit
 74 S. thence E. 20. chs. estab. 1/6 cor. 40 ch. estab.
 1/6 cor. 60. chs. estab. 1/6 cor. 60. chs. ~~find Cottonwood Creek~~
 and off set 10 chs North thence E. 14 chs makes 20 chs being
 E. link Sec. 6, from which I ran N. 10. ch. but after diligent
 search could not find Sec. cor. I re-estab. same with stone
 pits & W. in each sec. and mound N.

Friday April 12th 1895.

From the cor to Secs 19 and 30, on W. side T. 1. S. R. 1. W. I ran
 N. at 40 chs. find old 1/4 Sec. Stone firmly in ground
 pit & mound 12 links West at 80. chs. 79.63 chs. find
 30 Stone lying loose on ground 13 links N. at 80. chs I
 re-estab. Sec. cor on line pit dug at about 1/2 way
 and pit in each sec. and mound N. from which I ran
 North East 77 39° 10' W. 2.50 chs. has barn on stable S. 70°
 East 77 30° E. 2.50 chs dist. Peasest house East S. 35° W.
 about 4.50 chs dist. Nudge rats house East S. 68° W.
 about 6.00 chs. From this Sec. cor. I ran N. 10. chs and
 estab. cor. may centre of tree bearing N. 46° W. about 300 ch
 on S. 46° E. about 4.00 chs. land lying on N. side of it
 owned by Towgitchy. 20 chs set cor. in place and
 from the Sec. cor. I ran E. at 10 chs set cor. on
 N.W. corner of 20. ch. at 10 ch. N.E. cor.
 From same Sec. cor. I ran S. 10 ch. set cor.
 From N.E. Cor. of S.E. 1/4 of S.E. 1/4 of Sec. 8. T. 1. S. R. 1. W. I ran
 N. 20. chs. and re-estab. 1/6 cor. of 40. chs. re-est. 1/6 cor. on
 line bet Secs 8 & 17. thence I ran S. 20. ch and find old 1/4
 cor on line bet Secs 8 & 17.

Saturday April 13-1895.

From 1/4 cor. on line bet Secs 8 & 17. T. 1. S. R. 1. W.
 I ran S. 20.23 chs find 1/6 24 links E. firmly in ground
 I re-establish cor. at place where found by digging pits N.E. &
 and building mound on N. side. and find the course of
 this line to be 50° 41' E. From this last mound 1/6 cor. I
 I ran S. 20. chs. after diligent search could not find old
 cor. I re-estab. cor. stone and build mid of stone N. from
 which 1/6 cor. on E. line Sec 17. I ran N. 89° 01' E.
 From which I ran W. 20. ch 40 ch estab. 1/6 cor. from which I
 ran N. 20. ch. find old cor. a. find run N 45 part N. side
 of Episcopal Mission Grange N. 10° 30' W.
 From N.E. Cor. S.E. 1/4 of S.E. 1/4 of Sec. 8. T. 1. S. R. 1. W. I ran N. 20. ch
 & re-estab. 1/6 cor. from which I ran W. 20. ch & set cor. from which
 I ran S. 20. ch. & E. 20. ch. for Arroyo ch.