

Bishop) Monday April 15th 1895
 From a point 20 chs N. of Cor. to Secs 18 and 19, on the N. boundary
 of T. 1. S. R. 1. W., I ran E. 20 chs, S 10 chs, W. 20 chs, N. 10 chs, for
 Towyouwitey.
 From the same point above described, I ran N. 19⁵³ ch find old
 1/4 Sec Stone firmly in ground, 9 links N. 39⁵³ find old 1/6 cor
 8 links N. marked and firmly in ground. I re-estab same by
 digging pits N & S, and mound W. From which I ran N. N
 62⁴³ 20.92 find old Sec cor. on line firmly in ground,
 From 1/6 cor last described I ran E. 20 chs & estab 1/6 cor from
 which I ran N. 20.04 & estab 1/6 cor on Sec, line between Secs
 7 and 18, from which I ran E. 20 chs and find old 1/4 cor
 37²⁵ E 3⁶⁹ chs dist. ^{that} re-estab. some of point where
 found by digging pits E & W, and mound W. I also find 1/6
 cor. N 3¹⁵ E. From the 1/4 Sec Stone as last described, I find
 I ran N 22¹⁰ W. 20.12 ch and find 1/6 cor. Stone firmly in ground
 I dig pits N & S, and build mound W. from which I ran S 78⁹ 35 E
 20 chs.

(Spoonhunter?) Tuesday, April 16th 1895.
 From the S.E. Cor. of S.W. 1/4 of N.W. 1/4 of Sec. 3, T. 1. S. R. 2. E.
 I ran W. 20. chs. & N. 20 chs, and find old 1/6 cor. Stone 47. links
 W. From the S.E. Cor. of S. W. 1/4 of N.W. 1/4 of Sec. 3 I ran S.
 20. chs, and from the same described 1/6 cor. I ran N. 20. chs
 and re-establish 1/6 cor. with stone, pits N & S, mound W. From
 which I ran E. 20. chs, and not finding old cor. I re-estab.
 same on line, with stone - pits E & W. From which I ran S, at
 20. chs, find old 1/6 cor. on line. I dig pits N & S, and build
 mound W. 40. chs, find old Stone but line. I dig pits
 N & S, and build mound W 48. chs. bank of Little round Riv.

Wednesday April 17th 1895.

Re-established corners for Korkok, and also worked 1/2 day on
 Bishop's. Fence to Roberts school bears N. 0²⁵ W. 1/2 S.
 From 1/2 cor on line Sec 27 & 18, T. 1. S. R. 1. W., I ran S 20. chs
 re-establish 1/6 cor. south ground & N. of Trout Cr. for Bishop.
 40. chs. re-establish centre of Sec. D 18, as cor. for Bishop, E. of
 Creek

Thursday April 18th 1895.

(Yellow Dress.) From the centre of Sec. 28, T. 1. N. R. 1. E.
 I ran S. 20. chs, 20.49 chs, find 1/6 cor. 36 links E. which
 I do not move, dig pits N & S, mound W. 40.26 re-estab. 1/6
 cor. on line 60.26 find old 1/6 cor. firmly in ground 26. links
 W. 80.26 find old cor. 100.26 find old 120.26
 S. line T.

Friday April 19th 1895.

(Va. 17²⁷ E) (Yellow-belly.)
 From the Cor. to Secs 20-21-28 & 29, T. 1. N. - R. 1. E. I ran E. 20. chs
 & find 1/6 cor Stone firmly bedded on line. I dig pits E & W, and
 build mound W. From which I ran S 89²⁵ 50 E, 20. chs, and find
 1/4 cor. firmly in ground on line, I dig pits E & W, and build mound
 W. being the 1/6 cor. on line Sec. 28, 21 & 28. From this 1/4
 cor. I ran S. 10 chs, Little round Riv. bears E. 20. chs, & find
 pits of stone supposed to be 1/6 cor. I re-estab. same by pits N. & S
 mound W. long ch. S.E. Cor. N.E. 1/4 of N.W. 1/4 Sec. 28, in thick brush.
 From 1/6 cor. on line Cor. Secs. 21 & 28, I ran E. 20. chs
 find 1/6 cor Stone firmly in ground, 13 links south. I dig pits
 E & W, and build mound north of stone, on line bet. Secs. 21 & 28
 From which I ran N. 02⁰⁵ W. 20. ch find 1/6 cor. pits 9 and