

From which I ran N 89° 50' W, 20, a find 1/16 cor. stone on
 line, I dig pits and build mound, from which I ran N. 20.
 chs. do not find old 1/16 cor. ^{on Sec. 20, 21} I establish same stone pit N 4 S. Mon
 N. From which I ran N 89° 50' W, 20, chs. re-build old cor
 pits N 4 S. mound, W. on Sec. 20, 21, which is
 due N. from 1/16 cor. 20, chs. From 1/4 Sec. Stone above described
 I ran N 89° 50' W, and at 20, chs. found build 1/16 cor. on line
 E of Sec 20-21. From which I ran N. 89° 50' W. 20, chs. go
 old 1/16 cor. on line. I re-build same part N & S. mound
 from 1/4 Sec. Cor. E of Sec 20-21, I ran S 0° 20' E 20, chs. a
 find 1/16 cor. stone. I re-build same pits & mound.
 From this 1/4 Sec. Cor. Sec. Stone East due S, 40, chs.
 From S.E. Cor. of S. N 1/4 of S. E 1/4 of Sec. 20, I ran N. 20, chs.
 and found 1/16 cor. on line.

Saturday April 20th 1895.

From the 1/4 Sec. Cor. bet. Sec 2 18 & 19 on N. boundary of T. 1 S. R. 1 W,
 I ran W. 20 chs. re-build old cor. ^{at 20, chs.} build new cor.
 in center of Sec. 13, from which I ran N. 20, chs. & build cor.
 From bet. Sec. 13. I ran, & find old stone 1/16 cor. 9 1/2 links.
 N. I re-build same. From cor. bet. Sec. 13, Ran W. 20, chs.
 build cor. 3 chs. S 75° E, from White Horse's Cabin
 40, chs. build cor. on line bet. Sec. 13 & 14. From this 1/4
 Sec. Cor. bet. Sec. 13 & 14, I ran W. 20, chs. not finding old cor.
 I build same, on side of hill North of Creek, head Easterly.
 From which I ran S. 20, chs. not find, del. cor. I build one, in top of
 hill, from which I ran W. 20, chs. build cor. on top of
 hill. 40, chs. build cor. on S. side of hill. From which I
 ran S. 20, chs. and build cor. on line bet. Sec. 14 & 23
 From which I ran W. 20, chs. and establish cor. to Sec.
 14-15-22-23. 1. ch. N. of Creek, from which perpendicular
 cliff bears S 59° 38' W. on N. side Canon
 From this Sec. Cor. I ran W. 20, chs. build 1/16 cor. 40, chs. build
 1/4 Sec. Cor. bet. Sec. 15 & 22. From which I ran S. 20, chs. across
 creek & build 1/16 cor. on N. slope of hill. from this 1/16 cor. I ran W.
 20, chs. & build 1/16 cor. N. of Cr. from which I ran N. 20, chs.
 & build 1/16 cor. on Sec. 15 & 22, being the N. E.
 cor. of N. W 1/4 of N. W 1/4 of Sec. 22. line N. W. cor. of Kegewah allotment.

Monday

Apr. 22-1895,

From the 1/16 cor. 20, chs. N. of the cor. to Sec 2 18-19 on N. boundary
 of T. 1 S. R. 1 W. I ran W. at 20, chs. establish 1/16 cor. 40, 33 ch
 I find 1/16 cor. stone 3 1/2 links S. which re-build.
 From the cor. to Sec 2 14-15-22 & 23, T. 1 S. R. 2 W. I ran N. 20, ch
 & build 1/16 cor. N. W. Cor. Kegewah, & from same Sec. Cor. I ran
 S. 20, ch. bet 1/16 cor. 40, chs. at 1/4 Sec. Cor. on line bet. Sec
 22 & 23. From which I ran W. 20, chs. get cor. 40, ch. bet
 cor. on W. line Kegewah. From which Ran S. 20, ch. & set bet. S. W.
 Cor. From 1/4 Sec. Cor. bet. Sec. 22 & 23. I ran S. 20, ch. & set Kegewah
 S. line 1/16 cor. From which I ran E. 20, ch. bet 1/16 cor. 40, chs. set
 Kegewah S. E. Cor. from which I ran N. 20, chs. and set 1/16 cor.
 in center of sec. 23, 40 chs. set 1/16 cor.

Tuesday April 23rd 1895,

From the cor. to Sec 2 18 & 19 on N. boundary of T. 1 S. R. 1 W.
 I ran W. 20, chs. find 1/16 cor. 30 links S. lying above on ground,
 40, chs. do not find old cor. I build same on line. From
 which I ran S. 20, chs. & build 1/16 cor. pit N 4 S. mound W.
 From which I ran E. 20, ch. & find old 1/16 cor. lying in ground
 4 1/2 links S. which I re-build. From which I ran S. 20, ch. &
 re-build 1/16 cor. on 1/4 Sec. line pin W. in Sec. 24.