

(Finsonie) Saturday, April 27th 1895.
 From the S.E. cor. of S.W. 1/4 of S. W. 1/4 of Sec. 26, T. 1. S. R. 1. W., which is a sand-stone, firmly set and marked 1/16. Found in place, I ran W. on random line va 17° E. on the line bet Secs 26 & 35, at 20.70 ch find cor. to Secs 26-27-34 and 35. 70 links N. marked 1 groove on S. and 2 grooves on E. From this I find that the line just ran bears N 88° W, or var, 15° E. I there fore ran W., with va 15° - bet sec 27 & 34 at 20. chs. do not find old cor. I build ramp S. of Mill Cr, 20 links. 40. chs do not find old 1/4 cr. I build curve with stone and pole E & W. in Avenue trans S.E. From which I run S. at 20. chs. set 1/16 on S. of Mill Cr. 40. Chs set 1/16 on Ravine on large hill sloping N.W. From which I ran N. 20. chs. and set 1/16 cor. stone on N. side of Mill Cr. and on the 1/4 sec. line running W. in Sec. 34, 20. chs. S. of a cor. which I by Thence I ran S. 70. chs. and build 1/16 cor. on hill sloping N. 40. chs. built cor. 1/16 supposed S. boundary Tp. 1. S. R. 1. W. From which I ran W. 20. chs. along supposed S. bdy. of Tp. after diligent search in a radius of 5 chs do not find old cor. I Sec. Cor. I build ramp Sec, cor.

Sunday 28th 1895. no-work, began to rain in evening.

Monday April 29th 1895.
 Rained all day - no work.

Tuesday April 30th 1895.

Rained all day - no work.

Wednesday May 1st 1895.

Worked after noon in office 1/2 day.

Thursday May 2nd 1895.

From the N.E. Cor. of S.E. 1/4 of S.W. 1/4 of Sec. 36 T. 1. S. R. 2. W., I ran E. 20. chs. build 1/16 cor. 25 chs. marks N. 40.92 chs find E. cor. Tp. 1. S. R. 1. W. of 1/16 cor. From the 1/4 Sec. Cor. on the line between Secs 24 & 25. I ran N. and at 30. chs. built 1/16 cor.

Friday May 3rd 1895.

From the S.E. Cor. of S.W. 1/4 of N.W. 1/4 Sec. 19 T. 1. S. R. 1. W. I ran E. for Ginger 20. chs. set 1/16 cor. on top of ridge N.E. 40. chs. set 1/16 cor. in valley about S. chs W. of high bluff. On N.W. S.E. from which I ran N. 20. chs. Both as above.
 After-noon worked in office putting names etc.

Saturday May 4th 1895.

Worked on Shonkites' allotments, 4 White horse. all day.

Sunday May 6th 1895.

From the cor. to Secs 5-6-14 & T. 1. S. R. 1. W. from which the bank at Fort Washak Bears. N 67° 40' E. I ran N. 20. chs. do not find old cor. I build temporary cor. 40. chs. after diligent search do not find 1/4 cor. I build ramp cor. 60. chs. do not find old and build ramp 1/16 cor. from which I run Washakies house cor. N 10° W 2 chs. 20th ch. find old Sec cor. 57 build E. From this I cor. the bank bears 57° 3' - 57° E. From this Sec. cor. I ran S. 79° 45' E. at the Wind Riv. Pass line 20. chs. find 1/16 stone line loose N 44° W 50 links do I build new 1/16 cor. on line above do not 20.77 ch find old 1/4 cor stone 50 links N. I re-build gateway at point where found and thence I ran N. 40. ch & set 1/4 cor. long N.E. Cor. of