

(Moonbury) Thursday May 16th 1895
From N. W. Cor. of N. E 1/4 of N. E 1/4 of Sec. 22, T. 1. N. R. 2. W. I ran N. 20. chs. build 1/16 cor. from which I ran W. along Section road.

(Keosauqua) Friday - May 17th 1895.
From the cor. to Secs 26-27-34 & 35, T. 1. N. R. 2. W. Still handle Quarry S 71° 57' E. I ran N 89° 40' W. 20. chs. find old 1/16 cor 11 links N.

From the cor. to Secs 33 & 34, on S. boundary of Tps. 1. N. R. 2. W. Sound stone marked 300 & 200 W. N 75° 21' W. to S. edge of a perpendicular cliff of Mountain about 4 miles distant. See time bet. Secs 33 & 34. bears 71° 28' E. From this Sec. Cor. I ran S 89° 40' E 20. chs. find 1/16 cor stone firmly set. 5 links South 40' chs find 1/4 sec stone 2 links South 60. 1/16 chs find old 1/16 stone firmly set on line. from which the above Perpendicular cliff bears N. 76° 31' W. Tower on Reservation School bears S 82° 02' E

Saturday, May 18th 1895.

From the Cor. to Secs 33 & 34, on S. boundary of Tps. 1. N. R. 2. W. with perpendicular cliff bearing N 75° 21' W. I ran N 89° 40' W. to S. E. Cor. of S. W. 1/4 of S. W. 1/4 of Sec. 32. From which the perpendicular cliff bears N. 71° 11' W. thence I ran S 0° 53' W. 4 d. chs. upto this eve. 15 1/2 days in May

Sunday May 20th 1895.

(Good Mass. Footlock &c) From the Cor. to Secs 35 & 36, T. 1. N. R. 1. E. I ran N. (2 1/2 m) (8 allots)

Tuesday May 21- 1895

(School Lines) From the 1/4 Sec. Cor. on line Secs 33 & 34, T. 1. S. R. 1. W. with spine on school bldg bearing N 68° 13' E. I ran N. 0° 04' E, W. 20. chs find old 1/16 cor on line (From above 1/4 cor. the 1/16 cor. stone bears S 0° 25' W.) 40. chs build cor. in center of Sec. 3. from which tower on school bears S. 50° 16' E. I ran S 89° 45' E 20. ch. not find old cor. Grid Farm. From which I ran S 0° 04' E at 20. chs. not finding old 1/16 cor. I build one, N. W. about 10. chs from school bldg. From which I ran S 0° 06' E. 20. chs to 1/16. cor on bed. line from which school tower bears N 43° 50' E. Thence I ran S 0° 13' E 20. chs. find old 1/16 cor. firmly settled near fence 6 & 10. from which I ran S 0° 34' W. 20. chs. find old cor. 40. Chs. not find old cor. build one from which I ran S 0° 30' W (3 miles allots)

Wednesday May 22-1895.

From center of S. E. 1/4 of Sec 5, T. 1. S. R. 2-E. which is a tower in place, S. of Nelson Road. I ran S. at 20. chs. find old 1/16 cor. at 40. chs. not finding old cor. I build one at 60. chs. find old 1/16 cor. stone firmly in ground 108 links N. 82° 25' W. From which I find that the true Range S 12° 02' E. From which I ran N 89° 58' W. and find 1/4 cor 32 links N. from which I find that this line must run N 88° 03' W. From this 1/16 cor I ran