

June 26-1895- Survey made for David M Kay in Ogden Valley. From the cor for Sec 9, 9-10-15+16 which is a granite stone 2x10x5 ins. firmly set and marked with 4 nails on S. and 3 nails on E. edges and mound of clay W. I ran N on Va 17-30 E of at 5315 ft, roughly measured find old Sec. Stone 8x10 x 6 firmly set, 136 ft East. I rebuild old cor. at place found from which I find my line must have run N 0° 24' W. Evidently I ran N and at 80 chs. on the intersection of T.P. line do not find old Sec. cor. I estab. same.

June 27-1895. Surveyed E 1/2 of Sec. 33. T.P. 7. N.R. 2. E for Morgan Powell.

- 2-417. * Hebe Filmer to John Scovcroft, Pt Lot 5+6, - B-13, P.A. OCS, Beg. 3 r. N. E. Cor. Lot 6, - S. 10 r. W. 3 r. N. 10 r. E 3 r. to Beg.
- 180- * Polly Filmer Taylor to John Scovcroft, Pt lots 5+6, - B13, P.A. OCS, Beg. 11 r. E. of N.W. Cor. Lot 6 S 10 r. E. 3 r. N. 10 r. W. 3 r. to Beg.
- 70* Wm Filmer to John Scovcroft, conveys surplus between the tracts above described.
- 0-138 * John I. Carnahan to John Scovcroft, Beg. 3 rods E. of N.W. Cor. Lot 6, B13, P.A. OCS, S. 10 r. E. 3 r. N. 10 r. W. 3 r. to Beg.

