

along N. side, N. 69th. Sec 2 33 & 4, Ascending
 7325, ravine bears 84° E. 600. ridge bears 530° E.
 700. top ridge 530° E. thence descend 1235. bottom ravine
 545° E. 1630 ridge bears 540° E. 2100. nearly ravine 540° E
 2550. top of ridge S. thence descending 2640. set
 quartzite boulders 16x13x9 in 10 in inground marked 14 on
 N. side raised mound of stone 2 ft base 1 1/2 ft high on
 N. side of cor. 3000. ft bottom of rain 310 W.
 290. 3290. top ridge S. 3740. ridge S. 4040. both
 ravine S. (1764 - 1764 ft flag, on ridge on E side deep ravine
 bearing S 30° E called Cottonwood Canyon. 5196. 1 steel dry bed
 of Cottonwood Cr. 330° E. 5296. begin to ascend. 5596. ridge (flag)
 descending 740° E. Cottonwood Canyon has scattering 1000 ft. base
 along its bottom, which about 1 ch. wide.
 Cott. Can. is about 500. ft deep. and 20. chs wide at
 top, at 5280. set quartzite boulder in
 ground marked for cor. to Secs. 32 and 33. E land
 mountainous. No timber soil stony & bare.
 5796. bottom ravine bears 745° E. 5496. a small spring
 of fresh water rises and flows about 2 chs N.E. & strikes.

W. along S. line 32.
 ascending. (see above) 7032 ft ridge N.E. 7640. along
 N. slope of ridge set outy boulders some 16x12x5.
 3345. 80 top of ridge lat flag pole. thence descend along
 ridge 3640. begin to ascend ridge 5280. ft set boulder
 stone 20x10-7-15' inground 1/4 cor. to Sec 32 711 & 32
 on N. slope, dug pits 18x15x17 mid of earth 1/4
 cor.

on S. line
 ascending. 1500. top ridge 370° E thence along S. side ridge
 2310. 1 ravine 550° E - thence ascend. 2400. enter
 aspen brush 550. leave aspen brush. 2640. set 1/4 cor.
 set quartzite boulder stone. 18x12x10. 12 in inground for 1/4 cor.
 marked S.C. 14 on N. face, and mound of stone 12 ft base
 1 1/2 ft high N. of cor. thence ascending 3400. top of
 high ridge. Siding 340° E. 4050. both ravine slopes S 25° E.
 4333. flag. at top of ridge N + S. from which flag at
 S.E. Cor. 7 p. 4 to S. the S.C. Cor. bears 71200° to 11
 45 45 59. to S. of back sight. at 7 E. Cor. of T.P.
 of back sight. at Sta 4049.5 on 5th mile on N. side of
 T.P. the S.C. Cor. is

T.P. Cor. marked set 9 boulder 18x14x5. ground for

