

Standard  $\frac{1}{4}$  Cor.  
to Sec. 32, T. 5, N. R. 4 E

a quartzite boulder stone 15 X 10 X 6 10" in ground  
marked S. C.  $\frac{1}{4}$  on N. face, and mould  
of stone 2 ft base 1 1/2 ft high N. of cor.

□

Standard Cor. to  
Secs 31 & 32, T. 5, N. R. 4 E

a quartzite boulder stone 20 X 10 X 7 15" in ground  
for Cor. to Secs 31 & 32, marked S. C. on N. face and  
5 grooves on E & 4 grooves on W. face. built mould of  
stone 2 ft base 1 1/2 ft high N. of cor. dug pits 18 X 24  
1/2 ft across on E. side 1/2 ft deep & 1/2 ft deep  
and N. of cor. 7 ft deep & built mould of earth  
2 ft base N. of cor.