

Saturday Aug. 31 - 1895

0°09'E

N₁₁ Bet Secs 22 & 23,

(43. It to be
subtracted to
these

- From Cor. to Secs 22-23-26-27.
 I run N 0° 9' E, bet Secs 22-23
 Ascending
 400. 64.9 top of ridge 9 10° E. thence ascend along
 W. side by deep ravine
 2180 33.46 top of ridge bears S 45° W - N 45° E. Bring Co.
 head of Summit of Morgan Co.
 thence descend.
 640. 40.66 set ~~top~~ cobbler stone 16x8x6 10' in ground for 1/2 cor
 marked 4 in W. gas and stone W.
 in bottom of ravine N 45° W. 200 ft. deep
 thence over rolling ground ~~marked~~ ^{300 ft. deep} W. side of ravine
 370 = 43.61 ridge W. descent
 270 = 46.64 ravine W. ascent. 80 ft deep 400 ft wide
 -43-
 10 = 62.05 bottom of ravine 200 ft deep. Do close wide W.
 a spring 8 cts W.
 thence ascend steep hill.
 70-80. set quartzite cobbler stone 14x6x6, 9" in ground
 for cor to Sec 14-15-22-23. ^{marked} ^{md stone W.}
 on S. slope of ridge bearing S 45° E. N 45° W.

0°09'E
N₁₁ Bet 14, 15,

- Descend on E. side near, and S. Side North of Den Can.
 00. ¹⁰⁰ bottom of Wolf Den Can. bears N W.
 1843. 27.75 bottom E. side Wolf Den Can., N. W.
~~again~~ ^{at end of branch} N. W.
 1850 28.03 wagon road N. W.
^{camp to ascend,}
 1873 28.38 dry bed of creek N. W.
 1893 28.88 stream to ascend
 2200 33.32 top of ridge W. thence descend
 2640 40.00 set cobbler stone 14x8x6, 9" in ground for 1/2 cor. mound of stone W.
 2820. 42.72 bottom of canon, bears S 45° W. N 45° E. thence ascends
 4100 62.12 top ridge S 50° W. thence descend
 5263 79.74 photo conglomerate steep ledge 20 ft high 110° E.
 in draw W. 5 10° W. thence ascend
 5280. 80.00 set gray sand - stone 16x10x6 10' in ground for
 cor to Secs 10-11-14-15, marked with 2 grooves on E.
 and 4 grooves on S. edges, raised mound lower W. of cor.

Tuesday - Sep. 3 - 1895

- N. 0°09'E bet. Secs 10 & 11.
 ascending. Steep hill.
 900. 13.63 top of ridge bet E & W. high ridge thence descend
 240 18.78 end of scattering dead aspen
 240 33.94 bottom of canon N 70° W. bear dead aspen on excellent
 500 38.94 ridge of W. thence descend into canon,
 640 40.00 very gray sand stone 16x8x4 in ground
 for 1/2 cor. on N.W. slope of hill. md stone W.
 750 41.66 spring branch bears S 45° W. from a spring
 thence bears N 45° E. 10 cts. deep. thence ascend
 800 57.57 top of ridge N 40° E. & S 10° E. thence descend.
 900 66.66 head of ravine S 40° N.
 900 75.75 top ridge S 40° W. thence descend
 280 80.00 set cobbler stone 18x8x6 in ground for cor.
 to Secs 2-3-10 & 11 - md stone W. squares S 12 E.
 in head of ravine S 45° W.