

Sunday Sept 1-1895.

Went on a tour line bet

Secs 25 & 26.

Beg. at cor. to 23-24-25-26

Boulder, 14x8x8. 9" ground mound of stone
1 1/2 ft high 2 ft base,

Ft	Obs.	desc.
2640	40.00	desc. descending in ravine set quartzite boulder stone 18x10x8. 12" in ground for 1/4 cor. marked 1/4 on N. face raised mound of stone 1 1/2 ft high 2 ft base N. of cor. descend into ravine
2690	40.15	bottom ravine N 40° W.
3060	46.36	foot of slope at S side N. Fork Harris Cr. S 45° W
3133	47.47	and end of creek.
3172	48.06	road, thence ascend
3800	57.57	conglomerate ledge N 45°
4200	63.63	ridge S, N 15° W. S 15° E, 200 ft deep. 1000 ft wide
4600	69.69	ridge S,
5050	76.51	top of ridge S,
5290	80.15	cor. to Secs 22-23-26-27 heretofore described

Monday Sept 2-1895

W. on tour line bet Secs

22 & 27-

Ft	Obs.	desc.
225	34.1	bottom rav. N 15° W. Slope S 15° E.
500	7.52	thence ascend ridge S 15° E. thence descend.
1000	15.45	small rav. S 10° E, thence ascend.
1225	18.58	small ridge S,
1500	22.7	rav. S 15° E; thence ascend
2550	38.02	top of ridge S 15° W. thence descend
2640	40.00	set of boulder stone 18x12x6. 10" in ground for 1/4 cor. marked 1/4 on N. face raised mound of stone 1 1/2 ft high N. of base N. of cor. ravine S 15° W. thence ascend.
2900	43.94	top of ridge S 15° W. thence descend
3150	47.72	top of ridge S 15° W.
3200	48.43	set of boulder
3486.5	57.72	intersect line bet Secs 27 & 28 - 97.45 ft 30 ± 3' N from old Sec line. (At this point set boulder stone 18x6x6 10" in ground)
18.72	66.43	bottom ravine S 30° W. thence ascend
23.00	71.43	top of ridge S,
25.00	73.43	ridge S 10° E.
28.13	80.26	top of ridge S 40° W.

28.13 = 77.21