

Monday → Sept. 9-1895

Retrace line cut Sec 5

15-416,

Beg. at point 78.28 ch N. of cor. to Sec 5
14-15-22 & 22, 14 & 23,

1300 ft	19.70	bottom of gulch	340° W
1325	20.02	edge of	340° W
2500	37.88	bluff at S. side of gulch	thence ascend leading N.E. to Hood Dr.
2648	40.12	thence descend	
2700	40.90	find old 1/4 cor.	bouldery stone 8x8x10 firmly
2750	41.66	bluff on bluff	
2875	45.07	bottom of gulch	found 1/2 S.W.
3340	50.60	found 1/2 W.	ascend
48.00	69.70	top of hill	thence over level, land
4700	71.21	bottom of gulch	W.
4800	72.22	begin to ascend	
5275	79.92	intersect line ran W.	from Cor. to Sec 5 10-11-14-15

at 5179. Ft. 5284 find old Sec 5 - 276.5 ft E.
Tuesday Sept 10-1895

W. on random

cut. Sec 5 10 & 15,

✓

From the cor. to Sec 5 10-11-14 & 15 heretofore described I run N. along N. side of Hood Dr. Canyon

600	9.09	edge of	S	thence descend
1350	20.45	bottom ravine	320° W	thence ascend
1950	29.54	ridge	S, W	descend
2150	32.57	ravine	S, W	use
2400	36.86	ridge	S45° W	descend
2640	40.	set of boulders 20x6x6	12" in ground and stone	
2960	44.84	bottom ravine	340° W	ascend
3150	47.72	ridge	S40° W	thence over broken ground
4150	67.88	bluff	S40° W	
4270	69.70	bottom ravine	340° W	ascend
4550	68.94	bluff	S40° W	thence level
4700	71.21	descend		
4850	73.48	bottom ravine	S40° W	
4900	74.24	find old, see Cor. 121	get North a gray sand	

5179 78.67 intersect the line ran N. 09° E. 78.28 chs. N. from
E. line of this Sec. yesterday. at Sta 5275,
S.E. angle of intersection 90° 10'