

- Fl. ch
 48 17.40 Enter alfalfa field N. side Post 4, the N.W. cor. of this claim.
 Thence I ran $368^{\circ}35' W.$ along ^{wire fence} the ^{W. line} ~~W. line~~ of this claim 10 ft E. of wagon road.
 55 3.86 to post 5. of this claim
 Thence I ran $316^{\circ}18' W.$ along W. line claim near wagon road to post 6. of the claim.
 19 6.34
 Thence I ran $521^{\circ}50' E.$ along W. line of claim marked by fence & 10 ft E. of wagon road.
 7 1.62 to post 7. of this claim.
 Thence I ran $332^{\circ}29' W.$ along W. line of claim, wire fence, 10 ft E. of road.
 3.5 1.41 to Post 8 of the claim.
 Thence I ran $315^{\circ} W.$ along W. side of claim, wire fence 10 ft E. of road.
 21 3.34 to post 1 of the claim the piece of land all the land lying beyond Canal is cultivated to alfalfa and potatoes!!

Thursday Sept 26-1895.

- ✓
 N. on line Oct 8-417
 From S.E. Cor. Sec 9, adjoins Stone 15 X 8 X 6 bottom corner near W. side of wire fence S. line parcel Molas claim. N.W. of W. = boundary 15 X 12 X 6 1/2
 1.23 1.57 Wood road N.W. into Holley Can
 2.30 3.43 dry bed of creek at mouth of Holley Can course $510^{\circ} E.$
 3.00 4.14
 4.00 6.06 begin to ascend "hill" at mouth of Holley Can course $N 40^{\circ} W.$
 7.50 11.36 top of hill ascend along ground slope N.E.
 19.00 23.79 top of ridge $N 45^{\circ} W$ slope 40° on S. side Holley Can
 Thence descend along ground slope S.W.
 24.55 37.65 bottom of ravine of Can $545^{\circ} E.$ thence ascend abruptly along ground slope N.E.
 26.40 40. set of boulder stone $12 X 8 X 6$ 9" in ground $2 1/4$ cor. marked "c" on N. side raised mound stone $1 1/2$ ft high 2 ft base N. of cor.
 33.00 58.00 top of ridge. $S 40^{\circ} E.$ Thence along ground S. South
 38.50 58.33 bottom ravine S. ascend abruptly
 41.75 63.25 top of ridge S. Thence descend abruptly, down S.W. slope
 45.00 68.18 a spring of pure water $S 40^{\circ} E.$
 47.50 71.97 bottom of canon $S 40^{\circ} E.$ Thence along ground slope S.E. ascending
 52.00 80. set boulder stone $16 X 10 X 6$ in ground few cor. to Seas
 54.80 7-8 = 17-418. marked with 5 notches on S & 4 notches on S. edges raised mound of stone W. land mountainous - no timber soil good & 4 gate