

Saturday, Sept. 28th 1895.

N 0° 07' E on two lines

Cut. Secs 5 & 6.

74		
	do	From Cor. to 5-6-7-48. Run N 0° 07' E ascending on ground sloping S E, and along N. side of barrier 9,
1820	20.00	foot of abrupt ascent
2500	37.97	top of ridge's cut. little Coll. & Folley S 80° E.
2600	39.39	thence descend on ground slope N. E.
2600	40.00	near aspen S. 60° E.
		set 9. 10. Stone 15 X 12 X 6 9" in y. m. stone W.
2850	43.13	begin aspen ascend abruptly
3000	45.47	top of ridge N 70° E. thence descend abruptly
3000	46.97	bottom of canon N 30° E. barrier aspen ascend abruptly
300	57.57	top ridge E. thence over ground sloping E.
100	62.12	bottom of S. branch little Coll. Pass S 35° E. for 15 ch. thence over E. barrier
		thence ascend abruptly ground slope S
50	76.51	top of ridge N 80° E. thence descend ground slope N.
262	79.57	intersect standard cor. to Secs 31 & 32, mark some C.C. on S. face. Pass

Monday Sept 30-1895

S. on two lines cut Secs 7 & 8.

427	6.47	descending on ground sloping S. W.
52	6.34	dry bed of creek in Folley Cor. drain S 45° E.
		in angle of road S 45° E. N. 45° W.
		top of ridge to ascend side of canon on ground sloping N. E.
20	13.94	top of ridge S. 80° E. thence descend abruptly along ground slope S. E.
100	16.66	foot of abrupt descent in border of narrow ravine on ground slope E.
220	18.48	begin to ascend abruptly ground sloping N.
137	20.53	top of ridge E. descend abruptly, grad slope S.
550	23.45	bottom of canon S 80° E. thence ascend abruptly ground sloping N.
1900	28.78	top of ridge S 70° E. descend abruptly, along ground slope S. E.
160	31.81	bottom narrow E. ascend abruptly over ground slope N. E.
300	34.34	top of ridge S 45° E. descend abruptly on ground slope S. W.
460	37.27	bottom of canon S 40° E. ascend abruptly along slope N. E.
640	40.	set counter stone 12 X 10 X 6 9" in ground for the sec. Cor. marked N on W. face raised mound of stone W. of cor.
770	43.49	top of ridge S 35° E. thence descend abruptly on ground slope S. W.