

Ft.

Chs.

- 3700 56.06 Bottom of Cañon S 30° E. thence descend over ground slope N. E.
- 4360 65.15 top of ridge S 40° E. thence descend abruptly, ground slope S. E.
- 4650 70.45 Spring of pure water flows S 45° E. 2 chs & sinks.
- 4725 71.59 Bottom of cañon across S 45° E. thence ascend over ground slope N. E.
- 4825 73.10 top of ridge S 45° E. thence descend gr. slope S.
- 4950 75.00 Bottom of Cañon S 45° E. ascend slope N. E.
- 5280 80.00 set boulder stone 16x10x6 9" in ground for Cor. to Sec 7-8-17 & 18, marked 5 notches on E & 4. on S. edges Md. Stone W.

Tuesday, Oct 1<sup>st</sup> 1895

✓  
S, on random line bet Sec 17 & 18, descend over ground slope E. From Cor. to Sec 7-8-17 & 18-

- 200 3.03 bottom of ravine E. 20 ft below cor. thence ascend abruptly ground slope N.
- 700 10.60 top of ridge from S 80° E. 150 ft above Sec. Cor descend abruptly, on ground slope S. W.
- 970 14.69 bottom of ravine across S 85° E. 150 ft below ridge a Spring of pure water rises 10 chs S 35° E. 1 chs N. E. thence ascend over ground slope N. E.
- 1775 26.87 hub on top of ridge bearing S 75° E. 50 ft above ravine. thence descend abruptly on ground slope S. W.
- 2375 35.98 bottom of ravine S 70° E. about 200 ft below ridge thence descend along ground slope S. E.
- 2640 40.00 set boulder stone 16x12x6. 10" in ground for 14 ch marked 16 on N. face, raised mound of stone 1 1/2 ft high 2 ft across N. of cor.
- 2965 44.92 bottom of cañon ravine S 30° W. thence S. E. ascend on spur of ridge.
- 3100 46.97 spur. W. descend abruptly.
- 3350 50.75 bottom of cañon S 35° E. ascend.
- 3500 53.02 spur 20 ft above ravine S 10° E. ascend, on ground slope S. W.
- 3710 56.21 bottom of cañon E & N 10° W. going former ravine 2 chs E. ascend abruptly, S. slope
- 3900 59.09 top of ridge S 20° E. N 45° W. descend
- 4575 69.31 bottom of ravine S 45° E N 45° W. ascend abruptly
- 4630 70.91 top of steep ascent. thence over broken ground
- 5041 76.38 set iron 8" at intersect E & W. line 373 ft N. of the old cor. 5.65 chs  
at 3.15 17-18-19-20 which is a silver boulder