

Oct 2 - 1895.

Retrace line bet Sec 18-7 N.

Fe.	chs	From clearing cor. setal yesterday on the line bet Sec 18 & 19, Run N., ascent abruptly. Slope N.E.
1200	18.18	top of spur N. thence descend along ground
1400	21.21	20 ft N.W. bottom of canon course S 25° W, ascent abruptly
1652	25.23	ground level S.E. spur descen
2125	32.52	top of bottom canon S 10° W
2244	34.00	find old 1/4 cor. a boulder stone 20 x 12 x 10, 30 ft north marked 1/4. and pile of stones on spur of thence descend
2400	36.36	bottom canon S 10° E ascent abruptly
2640	40.40	30 ft N. set boulder stone 18 x 12 x 10 1/2" in ground 1/4 cor. marked 1/4 on N. face raised in soil 1/2 ft high 2 ft base N. of cor.
3389	51.33	top of high ridge S. descend abruptly
4100	62.12	bottom of canon S. near Weber quarry, ascent abruptly.
4888	74.06	intersect N. boundary 60 ft S of the cor. to Sec 13-18-19-24, which is a Red sandstone 20 x 10 x 7, firmly set, marked & written as described in the Surveyor General. Thence I run 389 & 21' 5".

Thursday Oct. 8 - 1895.

N. bet Sec 9 & 17 -

From the old cor. to Sec 5 89-16 & 17, which is a boulder stone 20 x 10 x 5 firmly set, marked & written as described in the Surveyor General. I ran N. on a trap line bet Sec 9 - 17, and at

444.7 ⁶³⁷ ~~bet boulder stone 14 x 11 x 8 9" in ground~~ intersect the N. line Sec 9, 236' 1/2 ft N. of the cor. to Sec 5. In Sec 8, heretofore I descended at this point I set a boulder stone 14 x 11 x 8, 9" in ground S.W. cor. of Sec 9, marked C. on E. face. 4 notches on S. & 2 on N. side. ^{dig pit 18 x 15 x 12 N.E. 7'} & raise mound of earth 2 ft high & 4 ft base N.E. of cor.

I re-establish the above old cor. by digging pit, 18 x 15 x 7 ft S. and raising mid of earth 4 ft base 12 ft high S of cor.