

Friday - Oct 4 - 1895.

Prog. at W. C. Free, Sec. 9 -

- N. 22° 22' E along wire fence, 2 ch. N of bottom of hill, and alfalfa field.  
over gravelly sand.
- 275 4.16 s. side washbank  
300 4.54 bottom of washbank E.  
340 5.15 N. side descent  
600 9.09 bottom of descent thence ascend.  
1100 16.16 fence for gate way,  
1200 18.18 from S. crossing  
2006 30.40 division fence line S 63° 45' E.  
2230 33.78 fence N 21° W S 21° E.  
2330 35.30 fence N 23° E S 23° W.  
2400 36.36 Jacobs. Mules house 100 ft E.  
2566 38.31 Cor. N 2° 1, 30 ft N. of wire fence,  
Cor. N 2° 1 is about 1/2 ch. N. of foot of hill.  
a stake in pile of stones
- Thence N 53° 05' E.  
along ground sloping S.E. and on crest of bluff  
about 50 links short of bottom.  
360 4.54 to Cor. N 2° 2 a stake in pile of stones
- Thence N 23° 15' E  
along crest or bow of hill sloping E  
621 9.40 intersect wire fence N 10° W. 7 S 10° E, 100 ch  
N. West base of 75 links S.E. of fence in part  
700 10.60 about 25 ft E of fence & 30 ft N. of bottom  
of hill
- 1315 19.24 bottom wood creek (dry) S 50° E  
1345 20.27 gate or gate way in fence  
1463 22.16 Meander Cor. 1 on sec. line bet Sec 4 & 9.
- Thence N 26° 08' E in Sec 4,  
along W. side of wire fence, along ground  
1400 21.21 sloping S.E.  
begin to descend along ground sloping E. 20 ft  
& to gate  
1500 27.27 top of abrupt descent about 20 ft high.  
1850 28.03 bottom  
1885 28.53 dry end of creek S 40° E from Big Cotton and  
1925 29.16 Cor. N 2° 1, in Sec. 4 a stake in pile of stones
- Thence from N 80° 15' E  
48 .73 wire fence N 30° E, S 30° W, 10 ft S. 30° W.  
150 2.27 gun. cor. of fence  
188.5 2.85 wire fence S 35° W.  
Cor. N 2 - near fence post in pile of stones  
3 ft N. of fence
- Thence from N 67° 46' E, 3 ft N. of wire fence  
285 4.31 descending on low ground.  
302 4.57 irrigation ditch S 70° W, 1/2 ch. S. side  
Cor. N 2 3. in pile of stones at S. side of ditch, 1 ch. wide leading  
N. 4 S 26° 05' E. and S 22° 03' W, about 300 ft long  
& 4 ft deep  
Thence from S 36° 05' E. along S. side of  
667 10.11 in creek bed.  
Cor. N 2 4 3 ft N. of wire fence and side of road  
and 1/2 ch.