

Chains, Pits, impracticable
Land mountainous and broken,
Soil stony; 4th rate,
no timber
Mountainous land 75, 86 lbs.

(2) August 15-1895.

Page 11

August 15-1895 at 9th 45th P.M. 2 m. b. and at 10th 11th P.M.
Migmatite standard-bail road bars, I observe Poles
at eastern elongation in accordance with instructions in
the Manual, at the cor. of Secs 25-26-25 and 26,
and mark a point in the line thus determined by a tack
in a wooden plug set in the ground 5. chs. N. of my station.

August 16th at 8.9 A.M. I lay off the azimuth of Poles
1st 60th to the west and mark the true meridian thus
determined by a tack driven in a wooden plug set in
the ground 5. chs. west of the point established last
night.

Thence I run
N 0^o 10' E. lat. Secs, 25 & 26.

Ascending over stony ground,
Bottom of ravine bears S 50^o E & N 30^o W. Begin to ascend

1.30 Speed 8
3.50 Bottom of ravine bears S 20^o W. & N 20^o E. Begin ascent of rocky
5.00 hill slope.

12.35 Top ridge 200 ft high bears E & W. Begin descent,
36.00 Spring branch, (very small, in bottom of ravine, drains N. 50^o W.

40.00 Set quartzite boulder stone 15 x 10 x 8 ins 10 chs in the ground
for 1st Sec. cor. marked 1/4 cor W. face; and raised mound
of stone 2 ft base, 1 1/2 ft high N. of cor. Pits impracticable

54.00 Bottom of S. Fork of Harris Canyon 500 ft deep, bears S 50^o E
and N 30^o W. Begin to ascend N. side of canon,
77.30 Top of ridge 400 ft above bottom of canon. Begin descent.
80.00 Bottom of ravine bears W.

Set boulder stone 14 x 8 x 8 ins in the ground for cor.
of Secs 23-24-25 and 26, marked with 12 notches
on S. and 1 notch on E. edges; and raised mound
of stone 2 ft base, 1 1/2 ft high N. of cor. Pits impracticable

Land mountainous
Soil stony; 4th rate,
no timber
Mountainous land 80⁰⁰ lbs.

(4)

First on a random line lat. Secs, 24 and 25.

40.00 Set trap, 1/4 Sec. cor
80.20 Intercept E. base of Sp. 2 lbs S. of the cor. of Secs 19-24-25
and 30, which is a boulder stone 7 x 6 x 6 ins, above ground
family set, marked and returned as described by the
surveyor general

Thence I run
S 89^o 59' W, on a true line lat Secs, 24 and 25.

10.25 Descend over stony ground.
Small Spring branch, in bottom of S. Fork of Harris Canyon, 500 ft deep, bears S 70^o W,
ascend over rough broken hill side 23rd Sec.

40.10 Set quartzite boulder stone 18 x 8 x 8 ins 12 chs in the ground
for 1/4 Sec. cor. marked 1/4 cor W. face; and raised mound
of stone 2 ft base, 1 1/2 ft high, N. of cor. Pits imp

40.70 Top of ridge bearing N 4th S. Descend
47.70 Bottom of ravine draining S.W. Begin ascent
52.20 Top of ridge bearing S 70^o W. & N 70^o E, & begin descent.