

80.20

The cor. of Secs, 23-24-25 & 26,
Land mountainous,
Soil stony, and sandy; 3rd and 4th rate.
No timber,
Mountainous land 80.20 chs. (5)

N. on a true line bet. Secs 23 & 26.

40.00

Descend ~~down~~ bottom of ravine, heavy N.
Set quartzite boulder stone 18x10x8 ins, 12 ins in the
ground part 1/4 Sec, or marked 1/4 on 7. Sec, and raised
a mound of stone 2 ft base, 1 1/2 ft high N. of cor.
Pits impracticable.

40.75

42.00

46.30

Bottom of ravine, course N 40° W. Begin ascent,
Top of ridge spur. Descend again. Descend, 500 ft deep
Bottom of N. fork of Harris Cañon, ~~and~~ 500 ft deep
Course S. 45° W.

47.80

48.00

47.50

43.50

Top of ridge (dry) drain S 45° W. Begin steep ascent
Wood road leading S 45° W. & N. 45° E. Begin steep ascent
Columbian ledge 20 ft high ~~at~~ S. nearly N. 45° S
Top of high ridge 300 ft above bottom of cañon, heavy N. 45° S,
Begin to descend.

69.75

Bottom of ravine 200 ft deep. Course S 15° E,
a small spring of pure cold water in local basin
S 15° E about 100 chs dist above mouth of this cañon.
Begin ascent.

66.50

80.00

Top of ridge 200 ft above bottom of ravine course S.
Begin to descend
Set quartzite boulder stone 16x12x6 ins 11 ins in the ground
in cor. of Secs 22-23-26 and 27, marked with 2 white lines
on S. and 2 inches on E. edges; and raised a
mound of stone 2 ft. base 1 1/2 ft. high W. of cor
Pits impracticable

Land mountainous, and broken
Soil stony, clay and loam, 3rd & 4th rate
No timber,
Mountainous land 80.00 chains. (6)

N. on a true line bet. Secs. 22 and 27,

71.40

75.00

75.50

72.25

38.60

Descending over stony ground
Bottom of ravine 100 ft below the cor. course S 15° E. Begin ascent
Top of ridge course S 15° E. Begin descent
Bottom of ravine 20 ft deep. course S 10° E. Begin ascent,
Top of low ridge course S. Begin descent

40.00

Bottom of ravine 20 ft deep. course S 15° E. Begin ascent
Top of ridge 200 ft above bottom of ravine, course S 15° W. N 45° E,
Begin to descend, W. slope,
Set boulder stone 18x12x6 ins in the ground
for 1/4 Sec Cor, marked with 1/4 on N. face, and raised
a mound of stone 2 ft base, 1 1/2 ft high N. of cor
Pits impracticable

43.90

47.75

48.50

66.50

Bottom of ravine 150 ft deep. course S 15° W. Begin ascent
Top ridge 75 ft above ravine course S 15° W. Begin descent
Wash divides ridge
Bottom of ravine 200 ft below ridge, course S 30° W,
Begin to ascend.

71.50

73.50

73.75

Top of spur. Begin to descend
Bottom of ravine 70 ft below spur
Intersect the sec. line 143 chs. S. of the old cor. of Secs.
21-22-27 and 28, which is a boulder stone 8x6x6 in
above ground, firmly set, marked, and witnessed as described